



**PROJECT ENDS  
STA. 520 + 13**

**PROJECT BEGINS  
STA. 513 + 36.70**

**PAVEMENT MARKING NOTES:**  
 ALL FINAL PAVEMENT MARKINGS SHALL BE THERMOPLASTIC (OF THE EXTRUDED TYPE) AND SHOULD BE PLACED IN ACCORDANCE WITH 'DISTRICT ONE TYPICAL PAVEMENT MARKINGS DETAIL'. (TC-13)  
 ALL RAISED REFLECTIVE PAVEMENT MARKINGS SHALL BE PLACED IN ACCORDANCE WITH THE DISTRICT ONE 'TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKER DETAIL'. (TC-11)

**LANDSCAPING NOTES:**  
 1. TOPSOIL, 4" SHALL BE PROVIDED IN ALL AREAS OF SEEDING.  
 2. APPLY NITROGEN FERTILIZER NUTRIENT, PHOSPHORUS FERTILIZER NUTRIENT AND POTASSIUM FERTILIZER NUTRIENT TO ALL SEEDING AREAS.

FILE NAME = P141309-shr-pmk.dgn	USER NAME = banks1	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>U.S. ROUTE 12/IL. ROUTE 59 @ BONNER ROAD PAVEMENT MARKING &amp; LANDSCAPING PLAN</b>			F.A.P. RTE: 334	SECTION OR-N	COUNTY LAKE	TOTAL SHEETS 40	SHEET NO. 16
	PLOT SCALE = 50.0000' / 1" IN.	CHECKED -	REVISED -		SCALE: 1" = 50'			SHEET NO. OF SHEETS	STA. 507+00.00 TO STA. 522+00.00	ILLINOIS FED. AID PROJECT		
	PLOT DATE = 4/4/2011	DATE -	REVISED -					CONTRACT NO. 60L20				