

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 344	543 R-HB-BR	DUPAGE	19	3

CONTRACT NO. 60L52

SUMMARY OF QUANTITIES

CODE NO	DESCRIPTION	UNITS	TOTAL QUANTITY	CONSTRUCTION TYPE CODE: 0014			
				URBAN 100% STATE	SN 022-1115		
67100100	MOBILIZATION	L SUM	1	1			
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1			
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1			
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1			
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1	1			
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	267	267			
X0325748	ACRYLIC COATING	SQ YD	46	46			
X0325749	FIBER WRAP	SQ FT	418	418			
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	1855	1855			
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	34	34			
Z0021907	SILICONE JOINT SEALER, 1.75"	FOOT	555	555			
Z0021914	SILICONE JOINT SEALER, 2.75"	FOOT	140	140			
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4			
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	35	35			

ILLINOIS DEPARTMENT OF
TRANSPORTATION

SUMMARY OF QUANTITIES

Rev.