

SUMMARY OF QUANTITIES

90% FED.
10% STATE
URBAN

PAY ITEM NUMBER	DESCRIPTION	UNIT	TOTAL QUANTITY	0021 SAFETY
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	5	5
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	217	217
25000210	SEEDING, CLASS 2A	ACRE	0.04	0.04
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4
25100630	EROSION CONTROL BLANKET	SQ YD	217	217
40600895	CONSTRUCTING TEST STRIP	EACH	1	1
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SQ YD	464	464
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	94	94
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2,413	2,413
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	163	163
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6
63200310	GUARDRAIL REMOVAL	FOOT	130	130
64200105	SHOULDER RUMBLE STRIPS	FOOT	5,050	5,050
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	6,224	6,224
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,075	2,075
* 72000100	SIGN PANEL - TYPE 1	SQ FT	105	105
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	18	18
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	13	13
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	230	230
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	12,200	12,200
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	155	155
78200420	GUARDRAIL MARKERS, TYPE B	EACH	5	5
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	6	6
78300100	PAVEMENT MARKING REMOVAL	SQ FT	3,745	3,745
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	155	155
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	50	50
X2503100	MOWING	UNIT	20	20
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51	51
X0326898	CENTER LINE - RUMBLE STRIP - 16"	FOOT	3,594	3,594

* 72400710 RELOCATE SIGN PANEL - TYPE 1 SQ FT 2 2
 * 70300240 THERMOPLASTIC PAVEMENT MARKING - LINE 6" FOOT 88 88
 * 70300260 THERMOPLASTIC PAVEMENT MARKING - LINE 12" FOOT 142 142

△ - NON-PARTICIPATING
 * - SPECIALTY ITEMS

Rev. 6-3-11

FILE NAME =	USER NAME = .USER.	DESIGNED - EF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL 19 - EAST OF DES PLAINES RIVER RD TO IL 171 SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
FILEL		DRAWN - EF	REVISED -			345	2010-118-1	COOK	17	3	
	PLOT SCALE = 50,0000' / IN.	CHECKED - RS	REVISED -			SCALE: NTS SHEET NO. 1 OF 1 SHEETS STA. TO STA.					
	PLOT DATE = 4/11/2011	DATE - 04-12-2011	REVISED -			ILLINOIS FED. AID PROJECT CONTRACT NO. 60M55					