

INDEX OF SHEETS

STATE STANDARDS

GENERAL NOTES

<u>SHEET NO.</u>	<u>DESCRIPTION</u>	<u>STANDARD NO.</u>	<u>DESCRIPTION</u>
1	TITLE SHEET	000001-06	TYPICAL SYMBOLS, ABBREVIATIONS AND PATTERNS
2	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES	420001-07	PAVEMENT JOINTS
3	SUMMARY OF QUANTITIES	420701-02	PAVEMENT FABRIC
4	GENERAL LOCATION MAP	442101-03	CLASS B PATCHES
5	SUMMARY OF PATCHING SCHEDULE	701400-05	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
6-9	PATCHING SCHEDULE	701401-00	LANE CLOSURE, FREEWAY/EXPRESSWAY
10	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT (BD-24)	701411-07	LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMPS
11	FREEWAY ENTRANCE AND EXIT RAMP CLOSURE DETAILS (TC-08)	701426-04	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPERATIONS
12	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS AND DRIVEWAYS (TC-10)	701427	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS ≤ 40 MPH
13	TYPICAL APPLICATIONS: RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) (TC-11)	701446-02	TWO LANE CLOSURE FREEWAY/EXPRESSWAY
14-15	MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS (TC-12)	701601-07	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
16	DISTRICT ONE TYPICAL PAVEMENT MARKINGS (TC-13)	701606-07	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
17	TRAFFIC CONTROL AND PROTECTION OF TURN BAYS (TO REMAIN OPEN TO TRAFFIC) (TC-14)	701701-07	URBAN LANE CLOSURE, MULTILANE INTERSECTION
18	PAVEMENT MARKING LETTERS AND SYMBOLS FOR TRAFFIC STAGING (TC-16)	701901-01	TRAFFIC CONTROL DEVICES
19	TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)		
20	ARTERIAL ROAD INFORMATION SIGN (TC-22)		
21	STANDARD TRAFFIC SIGNAL DESIGN DETAILS (TS-05)		

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "JULIE" AT (800) 892-0123 OR 811 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED)

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE (OR TOLLWAY) PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT (OR ISTHA)

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

ALL PAVEMENT PATCHING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE ENGINEER SHALL CONTACT LAWRENCE HILL, AREA TRAFFIC FIELD ENGINEER AT (815) 485-6475 MINIMUM OF TWO (2) WEEKS PRIOR TO PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

DOUBLE LANE MARKERS ARE TO BE USED AS SHOWN ON THE DISTRICT ONE DETAIL "TYPICAL APPLICATIONS - RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" SHOWN IN THE PLANS.

THE EXISTING ROADWAY TYPICAL SECTION IS ASSUMED TO BE 10 INCHES OF PORTLAND CEMENT CONCRETE (PCC) PAVEMENT.

NO PATCHING IS TO BE DONE WITHIN FIFTY (50) FEET OF ANY RAILROAD CROSSING WITHOUT OBTAINING THE PROPER RAILROAD PROTECTIVE LIABILITY INSURANCE.

THE MINIMUM CLASS B PATCH DIMENSIONS SHALL BE A LENGTH OF 6 FEET AND A WIDTH THAT INCLUDES THE FULL WIDTH OF THE TRAVEL WAY.

FOR ALL PATCHES LOCATED IN THE MIDDLE LANE OF A ROUTE WITH A 3-LANE CROSS-SECTION (PER DIRECTION), CLASS PP-3 CONCRETE IS TO BE USED.

FOR ALL EXPRESSWAY LOCATIONS (MAINLINE AND RAMPS), CLASS PP-3 CONCRETE IS TO BE USED.

FOR INTERSECTION PATCHES, CLASS PP-5 CONCRETE IS TO BE USED. LOCATIONS TO BE DETERMINED BY THE RESIDENT ENGINEER.

JOINT SEALING FOR CLASS B PATCHES IS TO BE REPLACED WITH A SOLID PLASTIC BOND BREAKER (1/8" X T/3"; WHERE T IS EQUAL TO THE THICKNESS OF THE PATCH). THE COST OF THE SOLID PLASTIC BOND BREAKER IS TO BE INCLUDED IN THE COST OF THE CLASS B PATCH.

ANY DETECTOR LOOPS DAMAGED BY MILLING SHALL BE REPLACED IN KIND. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO QUANTIFY LOOP REPLACEMENTS NEEDED AND PROVIDE THE RESIDENT ENGINEER THIS INFORMATION PRIOR TO GRINDING OR REMOVAL.

FILE NAME =	USER NAME = VelichkovVV	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\pwidot\velichkovvv\d0259786\design\dgn		DRAWN -	REVISED -			VAR.	2011-001-PP	WILL	21	2
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -			CONTRACT NO. 60N89				
PLOT DATE = 4/14/2011		DATE -	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				
					SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.