

URBAN
100%
STATE

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES							CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
				0005															
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10															
40600300	AGGREGATE (PRIME COAT)	TON	51	51															
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	76	76															
40600895	CONSTRUCTING TEST STRIP	EACH	1	1															
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	764	764															
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2851	2851															
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	25454	25454															
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70300100	SHORT TERM PAVEMENT MARKING	FOOT	4593	4593															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1531	1531															
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	597	597															
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	50519	50519															
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1710	1710															
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	510	510															
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	553	553															
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	225	225															
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	983	983															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	983	983															
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	807	807															
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	745	745															
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1															

* SPECIALTY ITEM