

				CONSTRUCTION CODE	
				100% LAKE CD.	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	
28100203	STONE RIPRAP, CLASS A2	TON	13	13	
28200200	FILTER FABRIC	SQ YD	59	59	▲
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1808	1808	
40600300	AGGREGATE (PRIME COAT)	TON	27.1	27.1	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	60	60	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	887	887	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1043	1043	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	268	268	
44004250	PAVED SHOULDER REMOVAL	SQ YD	2687	2687	
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	5	5	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	221	221	
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1	
* 50105220	PIPE CULVERT REMOVAL	FOOT	105	105	
5421A012	PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY)	FOOT	32	32	▲
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	16	16	
5421A030	PIPE CULVERTS, CLASS A, TYPE 1 30" (TEMPORARY)	FOOT	12	12	
550A0060	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	145	145	▲
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	52	52	▲
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	84	84	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	59	59	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	265	265	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	321	321	
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	68	68	▲
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	365	365	▲
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2	▲
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1	▲
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1	▲
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	1	1	▲
54247110	GRATING FOR CONCRETE FLARED END SECTION, 18"	EACH	1	1	
54247130	GRATING FOR CONCRETE FLARED END SECTION, 24"	EACH	1	1	▲

* SPECIALITY ITEM

FILE NAME =
sh-t-soq002.dgn

USER NAME = IDOT

DESIGNED - EJM

REVISED -

PLOT SCALE = 50.0000' / IN.

DRAWN - BK

REVISED -

PLOT DATE = 4/1/2011

CHECKED - GFL

REVISED -

DATE - 12/17/10

REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

▲ Rev. 6-6-11

Rev.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	128-I-3	LAKE	128	6
CONTRACT NO. 60P33				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				