

				CONSTRUCTION CODE	
				100% LAKE CO.	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	5135	5135	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	2746	2746	
20101000	TEMPORARY FENCE	FOOT	8512	8512	
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	50	50	
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	50	50	
20200100	EARTH EXCAVATION	CU YD	15,208	15,208	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1861	1861	
20400800	FURNISHED EXCAVATION	CU YD	1000	1000	
20800150	TRENCH BACKFILL	CU YD	140	140	
<del>21101815</del>	<del>TOPSOIL FURNISH AND PLACE, 1"</del>	<del>SQ YD</del>	<del>66872</del>	<del>66872</del>	
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	4067	4067	
<del>21101625</del>	<del>TOPSOIL FURNISH AND PLACE, 6"</del>	<del>SQ YD</del>	<del>14710</del>	<del>14710</del>	
21101805	COMPOST FURNISH AND PLACE, 2"	SQ YD	16,931	16,931	
25000210	SEEDING, CLASS 2A	ACRE	2.72	2.72	
25000310	SEEDING, CLASS 4	ACRE	2.11	2.11	
25000312	SEEDING, CLASS 4A	ACRE	0.27	0.27	
25000322	SEEDING, CLASS 5A	ACRE	2.11	2.11	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	525	525	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	525	525	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	525	525	
25100105	MULCH METHOD 1	ACRE	2	2	
25100630	EROSION CONTROL BLANKET	SQ YD	65872	65872	
25100115	MULCH METHOD 2	ACRE	2	2	
25100900	TURF REINFORCEMENT MAT	SQ YD	1864	1864	
25100125	MULCH METHOD 3	ACRE	2	2	
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	25	25	
25100135	MULCH METHOD 4	ACRE	2	2	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2282	2282	
28000305	TEMPORARY DITCH CHECKS	FOOT	432	432	
28000400	PERIMETER EROSION BARRIER	FOOT	7645	7645	
28000500	INLET AND PIPE PROTECTION	EACH	2	2	
28001000	AGGREGATE (EROSION CONTROL)	TON	12	12	
28100103	STONE RIPRAP, CLASS A2	SQ YD	40	40	

\* SPECIALITY ITEM

Rev.

FILE NAME = sht-soq001.dgn	USER NAME = IDOT	DESIGNED - EJM	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50,0000' / IN.	DRAWN - BK	REVISED -		330	128-1-3	LAKE	128	5				
	PLOT DATE = 4/1/2011	CHECKED - GFL	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 60P33				
		DATE - 12/17/10	REVISED -		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT								