

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES						CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
				0005										0005				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	128	128					X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1628	1628					
25200110	SODDING, SALT TOLERANT	SO YD	128	128					X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	6758	6758					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	32	32					X5539700	STORM SEWERS TO BE CLEANED	FOOT	410	410					
40600300	AGGREGATE (PRIME COAT)	TON	158	158					X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	37	37					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	60	60					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	766	766					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					Z0007420	SIDEWALK REPAIR (SPECIAL)	SO FT	150	150					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	477	477					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	67	67					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3314	3314					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
42001300	PROTECTIVE COAT	SO YD	233	233					44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	378	378					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	15160	15160					44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	227	227					
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	217	217					44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	151	151					
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	130	130					X4240500	PORTLAND CEMENT CONCRETE SIDEWALK, SPECIAL	SQ FT	150	150					
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	87	87					X4404700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	150	150					
60300105	FRAMES AND GRATÉS TO BE ADJUSTED	EACH	23	23														
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL-MO	3	3														
67100100	MOBILIZATION	L SUM	1	1														
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1														
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1														
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1														
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1														
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6168	6168														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16300	16300														
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	139	139														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	6398	6398														
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16300	16300														
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	139	139														
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	546	546														
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	492	492														
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	66	66														

* SPECIALTY ITEMS
 NON-PARTICIPATING ITEMS - 100% STATE