

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			NON-PARTICIPATING QUANTITY
				ROADWAY 0003	SIGNALS/LIGHTS 0021	TRAINEES 0042	
				QUANTITY	QUANTITY	QUANTITY	
20200100	EARTH EXCAVATION	CU YD	1,934	1,934			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	2,266	2,266			
20800150	TRENCH BACKFILL	CU YD	59	59			
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,305	1,305			
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	6,000	6,000			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	75	75			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	75	75			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	75	75			
25200110	SODDING, SALT TOLERANT	SQ YD	6,000	6,000			
25200200	SUPPLEMENTAL WATERING	UNIT	90	90			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	124	124			
28000305	TEMPORARY DITCH CHECKS	FOOT	42	42			
28000400	PERIMETER EROSION BARRIER	FOOT	635	635			
28000500	INLET AND PIPE PROTECTION	EACH	1	1			
28000510	INLET FILTERS	EACH	33	33			
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	481	481			
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	652	652			
35501320	HOT-MIX ASPHALT BASE COURSE, 9"	SQ YD	3,559	3,559			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14	14			
40600300	AGGREGATE (PRIME COAT)	TON	52	52			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	76	76			
40600990	TEMPORARY RAMP	SQ YD	395	395			
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	34	34			
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	64	64			
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,120	1,120			
42001300	PROTECTIVE COAT	SQ YD	966	966			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	4,325	4,290	35		
42400800	DETECTABLE WARNINGS	SQ FT	96	96			

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2005 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. - 384-00021 - EXPIRES 4/30/2011
 2/25/2011
 \\PLOT5\WORK\PH2\Tb
 \\C:\PLOT5\WORK\PH2\Tb
 090491-PH2-S00.shp



DESIGNED - DSH	REVISED - 1-19-11 PER VILLAGE
DRAWN - CJC	REVISED - 1-31-11 PER IDOT
CHECKED - LDH	REVISED -
DATE - 12/6/10	FILE - 090491-PH2-S00.shp

**VILLAGE OF SHOREWOOD, ILLINOIS
 BLACK ROAD & RIVER ROAD
 INTERSECTION IMPROVEMENT**

SUMMARY OF QUANTITIES

SCALE: NONE

STA. TO STA.

F.A.U. RTE. 0298 0396	SECTION 09-0028-00-CH	COUNTY WILL	TOTAL SHEETS 63	SHEET NO. 4
C-91-726-09		CONTRACT NO. 63562		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(805)				