CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE ROADWAY 0003 QUANTITY	SIGNALS/LIGHTS 0021 QUANTITY	TRAINEES 0042 QUANTITY	NON-PARTICIPATING QUANTITY
44000100	PAVEMENT REMOVAL	SQ YD	1,019	1,019			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	9,418	9,418			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,866	1,866			
44000600	SIDEWALK REMOVAL	SQ FT	3,459	3,459			
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	157	157			
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	8	8			
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	34	34			
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	35	35			
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	55	55			
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	243	243			
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1			
54247100	GRATING FOR CONCRETE FLARED END SECTION 15"	EACH	1	1			
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	19	19			
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	73	73			
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	89	89			
55100500	STORM SEWER REMOVAL 12"	FOOT	162	162			
55100700	STORM SEWER REMOVAL 15"	FOOT	32	32			
56400100	FIRE HYDRANTS TO BE MOVED	EACH	3	3			
60107600	PIPE UNDERDRAINS 4"	FOOT	125	125			
60207005	CATCH BASINS, TYPE C, TYPE 1 FRAME, CLOSED LID	EACH	1	1			
60207905	CATCH BASINS, TYPE C, TYPE 11 FRAME AND GRATE	EACH	2	2			
60207915	CATCH BASINS, TYPE C, TYPE 11V FRAME AND GRATE	EACH	2	2			
60236800	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	3	3			
60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	2	2			
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1			
60500050	REMOVING CATCH BASINS	EACH	2	2			
60500060	REMOVING INLETS	EACH	5	5			
67100100	MOBILIZATION	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2009, BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-001071- EXPIRES 4/30/2011
2/24/2010 4:00:54 PM ...\plotdriver\PDF22X34.plt
...\PLOTS\090491-PH2-TOI
u:\projects\063 SHOREWOOD\090491-BlackRiverPh\CADD\SURVEY\DRAWINGS\DGNS\090491-PH2-S00.sht

BAXTER & WOODMAN Consulting Engineers

DESIGNED - DSH	REVISED - 1-19-11 PER VILLAGE		
DRAWN - CJC	REVISED - 1-31-11 PER IDOT		
CHECKED - LDH	REVISED -		
DATE - 12/6/10	FILE - 090491-PH2-S00.sht		

VILLAGE OF SHOREWOOD, ILLINOIS
BLACK ROAD & RIVER ROAD
INTERSECTION IMPROVEMENT

SUMMARY OF QUANTITIES

SCALE: NONE STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0298 0396	09-00028-00-CH	WILL	63	5
	C-91-726-09	CONTRACT NO. 63562		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT	M-9003(385)	