

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			NON-PARTICIPATING QUANTITY
				ROADWAY 0003 QUANTITY	SIGNALS/LIGHTS 0021 QUANTITY	TRAINEES 0042 QUANTITY	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	6,447	6,447			
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	5,680	5,680			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,610	2,610			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	328	328			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9,592	9,592			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,706	2,706			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	837	837			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	166	166			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	728	728			
* 80400100	ELECTRICAL SERVICE INSTALLATION	EACH	1		1		
* 80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1		1		
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	37		37		
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	35		35		
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	20		20		
* 81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	535		535		
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	435		435		
* 81400100	HANDHOLE	EACH	3		3		
* 81400300	DOUBLE HANDHOLE	EACH	1		1		
* 81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	6		6		
* 81603070	UNIT DUCT, 600V, 2-1C NO.2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	5,084		5,084		
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	4,482		4,482		
* 81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	854		854		
* 82103250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 250 WATT	EACH	4		4		
* 82500350	LIGHTING CONTROLLER, BASE MOUNTED, 240VOLT, 100AMP	EACH	1		1		
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	80		80		
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	4		4		
* 8440116	RELOCATE EXISTING LIGHTING UNIT <i>SPECIAL</i>	EACH	4		4		

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 08-000211, EXPIRES 4/30/2011
 46253737.W
 12/27/2011
 ...\\p01-df\va-vp022234.dwt
 ...\\p1-dts\090491-ph2-500.sht
 ...\\p1-dts\090491-ph2-500.sht



DESIGNED	DSH	REVISED	- 1-19-11 PER VILLAGE
DRAWN	CJC	REVISED	- 1-31-11 PER IDOT
CHECKED	LDH	REVISED	-
DATE	12/6/10	FILE	- 090491-PH2-500.sht

VILLAGE OF SHOREWOOD, ILLINOIS
BLACK ROAD & RIVER ROAD
INTERSECTION IMPROVEMENT

SUMMARY OF QUANTITIES

SCALE: NONE

STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0298 0396	09-00028-00-CH	WILL	63	6
C-91-726-09		CONTRACT NO. 63562		
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003(385)				