

| CODE NO. | PAY ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION TYPE CODE | | | NON-PARTICIPATING QUANTITY |
|------------|---|-------|----------------|------------------------|------------------------------|------------------------|----------------------------|
| | | | | ROADWAY 0003 QUANTITY | SIGNALS/LIGHTS 0021 QUANTITY | TRAINEES 0042 QUANTITY | |
| * 85700205 | FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL | EACH | 1 | | 1 | | |
| * 87301215 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C | FOOT | 1,262 | | 1,262 | | |
| * 87301225 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C | FOOT | 2,344 | | 2,344 | | |
| * 87301245 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C | FOOT | 1,471 | | 1,471 | | |
| * 87301255 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C | FOOT | 1,519 | | 1,519 | | |
| * 87301295 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 20 3C | FOOT | 300 | | 300 | | |
| * 87301805 | ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C | FOOT | 40 | | 40 | | |
| * 87301900 | ELECTRIC CABLE IN CONDUIT, EQUIPMENT, GROUNDING CONDUCTOR, NO. 6 1C | FOOT | 505 | | 505 | | |
| * 87502500 | TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT. | EACH | 4 | | 4 | | |
| * 87702930 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 40 FT. | EACH | 1 | | 1 | | |
| * 87702950 | STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT. | EACH | 3 | | 3 | | |
| * 87800100 | CONCRETE FOUNDATION, TYPE A | FOOT | 16 | | 16 | | |
| * 87800150 | CONCRETE FOUNDATION, TYPE C | FOOT | 4 | | 4 | | |
| * 87800415 | CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER | FOOT | 52 | | 52 | | |
| * 88030020 | SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED | EACH | 4 | | 4 | | |
| * 88030110 | SIGNAL HEAD, LED, 1-FACE, 5-SECTION, MAST-ARM MOUNTED | EACH | 4 | | 4 | | |
| * 88030240 | SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED | EACH | 4 | | 4 | | |
| * 88102717 | PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER | EACH | 8 | | 8 | | |
| * 88200110 | TRAFFIC SIGNAL BACKPLATE, LOUVERED | EACH | 8 | | 8 | | |
| * 88700200 | LIGHT DETECTOR | EACH | 2 | | 2 | | |
| * 88700300 | LIGHT DETECTOR AMPLIFIER | EACH | 1 | | 1 | | |
| * 88800100 | PEDESTRIAN PUSH-BUTTON | EACH | 8 | | 8 | | |
| * 89500400 | RELOCATE EXISTING PEDESTRIAN PUSH-BUTTON | EACH | 1 | | 1 | | |
| * 89502500 | REMOVE TEMPORARY TRAFFIC SIGNAL INSTALLATION | EACH | 1 | | 1 | | |
| Z0001050 | AGGREGATE SUBGRADE 12" | SQ YD | 4,174 | 4,174 | | | |
| Z0030850 | TEMPORARY INFORMATION SIGNING | SQ FT | 104 | 104 | | | |
| * Z0033022 | CLEAN AND RELAMP EXISTING LUMINAIRE | EACH | 18 | | 18 | | |
| * Z0033072 | VIDEO VEHICLE DETECTION SYSTEM | EACH | 1 | | 1 | | |
| Z0042002 | POROUS GRANULAR EMBANKMENT, SUBGRADE | CU YD | 349 | 349 | | | |
| Z0056610 | STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH | FOOT | 48 | 48 | | | |

* INDICATES SPECIALTY ITEM

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 384-00101 - EXPIRES 4/30/2011
 809322 ILL
 2/2/2011
 ...\\net101\proj\APR\PH2\224.dwg
 ...\\net101\proj\APR\PH2\110
 ...\\net101\proj\APR\PH2\110
 ...\\net101\proj\APR\PH2\110



| | |
|----------------|-------------------------------|
| DESIGNED - DSH | REVISED - 1-19-11 PER VILLAGE |
| DRAWN - CJC | REVISED - 1-31-11 PER IDOT |
| CHECKED - LDH | REVISED - 2-14-11 PER IDOT |
| DATE - 12/6/10 | FILE - 090491-PH2-S00.sht |

**VILLAGE OF SHOREWOOD, ILLINOIS
BLACK ROAD & RIVER ROAD
INTERSECTION IMPROVEMENT**

| | |
|------------------------------|--------------|
| SUMMARY OF QUANTITIES | |
| SCALE: NONE | STA. TO STA. |

| | | | | |
|-----------------------|------------------------|--------------------|-----------------|---|
| F.A.U. RTE. 0298 0396 | SECTION 09-00028-00-CH | COUNTY WILL | TOTAL SHEETS 63 | SHEET NO. 7 |
| C-91-726-09 | | CONTRACT NO. 63562 | | FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-9003385 |