

SCHEDULE OF QUANTITIES

SIGN PANEL - TYPE 1		
STATION	SQ FT	REMARKS
BARNEY DRIVE		
20+10 LT 22'	6.25	W11-2 PEDESTRIAN SIGN 30" X 30"
20+10 LT 22'	2.00	W16-9P AHEAD PLAQUE 24" X 12"
PROJECT TOTAL	8.25	
T2000100		

INLETS, SPECIAL		
STATION	EACH	REMARKS
BARNEY DRIVE		
RT 20+38	1	S-1
LT 20+38	1	S-2
PROJECT TOTAL	2	
K602 240*		

METAL POST - TYPE A		
STATION	FOOT	REMARKS
BARNEY DRIVE		
20+10 LT 22'	12	PEDESTRIAN SIGN
PROJECT TOTAL	12	
T2900100		

AGGREGATE SUBGRADE 12"		
STATION	SQ YD	REMARKS
BARNEY DRIVE		
19+25 TO 21+00	736	
PROJECT TOTAL	736	
Z000 050*		

PAINT PAVEMENT MARKING - LINE 4"		
STATION	FOOT	REMARKS
BARNEY DRIVE		
19+25 TO 20+89	328	CENTERLINE (OBL. YLW)
PROJECT TOTAL	328	
T8001110		

STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH		
STATION	FOOT	REMARKS
BARNEY DRIVE		
LT 19+85 TO 20+10	24	PIPE-3
LT 20+10 TO 20+36	29	PIPE-4
PROJECT TOTAL	53	
Z005 610*		

PAINT PAVEMENT MARKING - LINE 6"		
STATION	FOOT	REMARKS
BARNEY DRIVE		
RT TO LT 20+92	68	CROSSWALK (WHT)
PROJECT TOTAL	68	
T8001130		

STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH		
STATION	FOOT	REMARKS
BARNEY DRIVE		
LT 19+45 TO 19+54	18	PIPE-5
PROJECT TOTAL	18	
Z005 612*		

SEEDING (SPECIAL)		
STATION	ACRE	REMARKS
BARNEY DRIVE		
RT 20+25	0.08	CHANNEL AREA
PROJECT TOTAL	0.08	
K1005421*		

STEEL CASINGS 16"		
STATION	FOOT	REMARKS
BARNEY DRIVE		
LT 19+42 TO 20+12	70	
PROJECT TOTAL	70	
Z006 500*		

FILE NAME = S:\PROJECTS\2010\12010100_B Barney Drive Over Rock Run\Trans.Cover.Etc.dgn

USER NAME =	DESIGNED - L.G.N.	REVISED -	
	CHECKED - G.F.S.	REVISED -	
PLOT SCALE =	DRAWN - L.G.N.	REVISED -	
PLOT DATE =	CHECKED - G.F.S.	REVISED -	

**ILLINOIS DEPARTMENT OF TRANSPORTATION
BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN
STATION 20 + 00**

**SCHEDULE OF QUANTITIES
STRUCTURE NO. 099-6474**

SHEET NO. 3 OF 3 SHEETS

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0330	08-00413-00-BR	WILL	33	7
WHA# 1201010		CONTRACT NO. 63571		
ILLINOIS FED. AID PROJECT BRM-9003162				