

SUMMARY OF QUANTITIES					PAVEMENT	
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE	
					000 5	
	20101700	SUPPLEMENTAL WATERING	UNIT	2	2	
	25200110	SODDING, SALT TOLERANT	SQ YD	244	244	
	40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1728	1728	
	40600300	AGGREGATE (PRIME COAT)	TON	17	17	
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	284	284	
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	748	748	
	42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	93	93	
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	330	330	
	42400800	DETECTABLE WARNINGS	SQ FT	96	96	
	44000157	HOT-MIX ASPHALT SURFACE REMOVAL 2"	SQ YD	8619	8619	
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	149	149	
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1141	1141	
	44000600	SIDEWALK REMOVAL	SQ FT	330	330	
	44201725	CLASS D PATCHES, TYPE I, 7 INCH	SQ YD	4	4	
	44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	71	71	
	44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	45	45	
	44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	38	38	
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	13	13	
	60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1	
	60266600	VALVE BOXES TO BE ADJUSTED	EACH	6	6	
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B6.12	FOOT	1141	1141	
	67100100	MOBILIZATION	L SUM	1	1	
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	468	468	
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	650	650	
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	228	228	
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	140	140	
	X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	374	374	
	Z0004518	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 5"	SQ YD	125	125	
	Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	42	42	
	X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2	

GENERAL NOTES

- BEFORE STARTING ANY EXCAVATION THE CONTRACTOR SHALL CALL "J.U.L.I.E." AT (800) 892-0123 AND (312) 744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION REQUIRED)
- UTILITIES INDICATED ON THE PLANS ARE PROVIDED FOR THE CONTRACTORS USE AND ARE BASED UPON INFORMATION AVAILABLE AT THE TIME OF THE ADVERTISEMENT FOR BIDS. THE OWNER AND ENGINEER DO NOT GUARANTEE THE ACCURACY OF UTILITY INFORMATION.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
- SCHEDULES INCLUDED IN THE PLANS HAVE BEEN PREPARED FROM FIELD NOTES. EXACT LOCATIONS FOR PATCHING SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER.
- THE THICKNESS OF HMA MIXTURE STATED IN THE SPECIFICATIONS IS THE NOMINAL THICKNESS. DEVIATIONS FROM THE NOMINAL THICKNESS WILL BE PERMITTED WHEN SUCH DEVIATIONS OCCUR DUE TO IRREGULARITIES IN THE EXISTING SURFACE OR BASE ON WHICH THE HMA SURFACE IS PLACED.
- ACCESS TO DRIVEWAYS SHALL BE MAINTAINED AT ALL TIMES BY LIMITING CURB AND GUTTER REPAIR TO ONE-HALF THE DRIVEWAY WIDTH AT ONE TIME AS WELL AS TEMPORARY AGGREGATE.
- THE REMOVAL AND/OR REPLACEMENT OF ANY DRIVEWAYS, PAVEMENT, CURB, SIDEWALK, ECT. SHALL BE ACCOMPLISHED BY MEANS OF A SAW CUT JOINT, AT THE DIRECTION OF THE ENGINEER. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE UNIT PRICE FOR THE VARIOUS ITEMS.
- ANY LOOSE MATERIAL DEPOSITED IN THE FLOW LINE OF DITCHES, GUTTERS OR OTHER DRAINAGE STRUCTURES SHALL BE REMOVED BY THE END OF EACH DAY BY THE CONTRACTOR AT THEIR EXPENSE.

* - INDICATES SPECIALTY ITEMS

FILE NAME = 10516-QUAN-01 - 1001 P01

USER NAME =

DESIGNED -- JPH

REVISED --

CHECKED -- PKB

REVISED --

PLOT SCALE =

DRAWN -- RG

REVISED --

PLOT DATE = 03-18-11

CHECKED -- AG

REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

KOSTNER AVENUE RESURFACING
147TH STREET TO 143RD STREET
SUMMARY OF QUANTITIES AND GENERAL NOTES

F.A.U.
RTE.

SECTION

COUNTY

TOTAL SHEETS

SHEET NO.

2404

11-00026-00-RS

COOK

10 2

CONTRACT NO. 63574

SCALE: NA

SHEET NO 2 OF 10 SHEETS STA. TO STA.

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-8003(775)