

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				BLIVIN STREET	80% FED 20% COUNTY URBAN BRIDGE 0011
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	190		190
44000100	PAVEMENT REMOVAL	SQ YD	771		771
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	125		125
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	137		137
44000600	SIDEWALK REMOVAL	SQ FT	375		375
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	46		46
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	128		128
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50104650	SLOPE WALL REMOVAL	SQ YD	440		440
50200100	STRUCTURE EXCAVATION	CU YD	267		267
50300225	CONCRETE STRUCTURES	CU YD	84.9		84.9
50300255	CONCRETE SUPERSTRUCTURE	CU YD	386.4		386.4
50300260	BRIDGE DECK GROOVING	SQ YD	584		584
50300280	CONCRETE ENCASEMENT	CU YD	61.0		61.0
50300300	PROTECTIVE COAT	SQ YD	1,095		1,095
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	3,276		3,276
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	89,560		89,560
50800515	BAR SPLICERS	EACH	82		82
* 50901750	PARAPET RAILING	FOOT	354		354
51201800	FURNISHING STEEL PILES HP14X73	FOOT	1,222		1,222
51202305	DRIVING PILES	FOOT	1,222		1,222
51203800	TEST PILE STEEL HP14X73	EACH	4		4
51500100	NAME PLATES	EACH	1		1
52100520	ANCHOR BOLTS, 1"	EACH	48		48
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1		1
54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	1		1
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	20		20
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	142		142
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	30		30
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	19		19
55100500	STORM SEWER REMOVAL 12"	FOOT	95		95

* SPECIALTY ITEMS

FILE NAME = W:\755-010 Blivin Phase II\CADD_Sheets\755010-int-500.dgn

B Bollinger, Lach & Associates, Inc.
ITASCA, ILLINOIS

USER NAME = dbruckelmeyer	DESIGNED - DBB	REVISED -
PLOT SCALE = 20.0000' / IN.	DRAWN - DBB	REVISED -
PLOT DATE = 4/6/2011	CHECKED - CRF	REVISED -
	DATE - 03-28-11	REVISED -

BLIVIN STREET OVER NIPPERSINK CREEK

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 4 OF 69 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00355-00-BR	MCHENRY	69	4
CONTRACT NO. 63583				
FED ROAD DIST NO. 1 ILLINOIS FED AID PROJECT				