

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				BLIVIN STREET	80% FED 20% COUNTY URBAN BRIDGE 0011
55100700	STORM SEWER REMOVAL 15"	FOOT	32		32
55100900	STORM SEWER REMOVAL 18"	FOOT	10		10
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	52		52
60107700	PIPE UNDERDRAINS 6"	FOOT	218		218
60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1		1
60201105	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME AND GRATE	EACH	1		1
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1		1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	1		1
60404800	FRAMES AND GRATES, TYPE 11	EACH	1		1
60500060	REMOVING INLETS	EACH	5		5
60603401	GUTTER OUTLET (SPECIAL)	FOOT	64		64
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	105		105
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	112.5		112.5
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1		1
63200310	GUARDRAIL REMOVAL	FOOT	167		167
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5		5
67100100	MOBILIZATION	L SUM	1		1
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	916		916
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4'	FOOT	415		415
* 78008200	POLYUREA PAVEMENT MARKING TYPE I - LETTERS AND SYMBOLS	SQ FT	61.2		61.2
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	481		481
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	20		20
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	7		7
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	6		6
* A2001224	TREE, ACER RUBRUM RED SUNSET (RED SUNSET RED MAPLE), 3" CALIPER, BALLED AND BURLAPPED	EACH	7		7
* A2007122	TREE, QUERCUS RUBRA (RED OAK), 3" CALIPER, BALLED AND BURLAPPED	EACH	7		7
* A2008024	TREE, TILIA CORDATA (LITTLE LEAF LINDEN), 3" CALIPER, BALLED AND BURLAPPED	EACH	6		6
X0325405	FILL EXISTING STORM SEWERS	CU YD	5		5
X0326474	DROP STRUCTURE NUMBER 1	EACH	1		1
X0426200	DEWATERING	L SUM	1		1
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	113		113

* SPECIALTY ITEMS

FILE NAME = W:\755-010 Blvin Phase II\CADD\Sheets\755010-ent-500.dgn



USER NAME = dbruckelmeyer
 PLOT SCALE = 20.0000' / IN.
 PLOT DATE = 4/6/2011

DESIGNED - DBB
 DRAWN - DBB
 CHECKED - CRF
 DATE - 03-28-11

REVISED -
 REVISED -
 REVISED -
 REVISED -

**BLIVIN STREET OVER
NIPPERSINK CREEK**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 5 OF 69 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	08-00355-00-BR	MCHENRY	69	5
CONTRACT NO. 63583				
FED ROAD DIST NO. 1 ILLINOIS FED AID PROJECT				