


SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SAFETY IMPROVEMENTS	
				80% FED	20% VILLAGE
				0021	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	44	44	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	673	673	
20800150	TRENCH BACKFILL	CU YD	3	3	
25200200	SUPPLEMENTAL WATERING	UNIT	111	111	
28000510	INLET FILTERS	EACH	10	10	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100	
42001300	PROTECTIVE COAT	SQ YD	2,732	2,732	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	115	115	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	22,178	22,178	
42400800	DETECTABLE WARNINGS	SQ FT	392	392	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	225	225	
44000300	CURB REMOVAL	FOOT	72	72	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	463	463	
44000600	SIDEWALK REMOVAL	SQ FT	2,194	2,194	
44201670	CLASS D PATCHES, TYPE I, 2 INCH	SQ YD	85	85	
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	60	60	
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	2	2	
60234200	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	5	5	
60600605	CONCRETE CURB, TYPE B	FOOT	72	72	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	585	585	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	48	48	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	234	234	
78008250	POLYUREA PAVEMENT MARKING TYPE I- LINE 12"	FOOT	264	264	
78008270	POLYUREA PAVEMENT MARKING TYPE I- LINE 24"	FOOT	26	26	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	196	196	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0017400	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED	EACH	18	18	
Z0017700	DRAINAGE AND UTILITY STRUCTURES TO BE RECONSTRUCTED	EACH	2	2	
Z0066500	STABILIZED DRIVEWAYS 7"	SQ YD	26	26	
X2520650	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	650	650	
X2520700	SODDING, SPECIAL	SQ YD	4,625	4,625	
X4400500	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	170	170	
X8140115	HANDHOLE TO BE ADJUSTED	EACH	1	1	
XX003313	REMOVE AND REINSTALL BRICK PAVER	SQ FT	14	14	
XX007761	BUFFALO BOX ADJUSTMENT, SPECIAL	EACH	2	2	

LEGEND
 - DENOTES SPECIALTY ITEM

JJB JAMES J. BENES & ASSOCIATES, INC.
 950 Warrenville Road, Suite 101, Lisle, Illinois 60532
 Tel. (630) 719-7570 • Fax (630) 719-7589

FILE NAME =	USER NAME =	DESIGNED -- BDH	REVISED --
		DRAWN -- SMP	REVISED --
		CHECKED -- BDH	REVISED --
		DATE -- 02-09-11	REVISED --

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 VARIOUS ROUTES

SCALE: NONE SHEET NO. 3 OF 25 SHEETS STA. _____ TO STA. _____

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1504	09-00090-00-SW	COOK	25	3
			CONTRACT NO. 63596	
ILLINOIS FED. AID PROJECT				