



PROJECT BEGINS
STA. 60+25.30

PROJECT ENDS
STA. 67+84.70

LEGEND

- [A] STRUCTURE TO BE ADJUSTED
- (A) STRUCTURE TO BE ADJUSTED WITH NEW FRAME AND LID
- [R] STRUCTURE TO BE RECONSTRUCTED
- (R) STRUCTURE TO BE RECONSTRUCTED WITH NEW FRAME AND LID
- * DETECTABLE WARNINGS ON SIDEWALK RAMPS
- [X] SIDEWALK REMOVAL
- (TRP) TREE ROOT PRUNING (BY OTHERS)
- (IF) INLET FILTERS

NOTES:

- 1) DRIVEWAY LIMITS ARE 2 FEET FROM EDGE OF SIDEWALK, UNLESS OTHERWISE NOTED.
- 2) PAVEMENT MARKINGS SHALL BE THERMOPLASTIC ON CAROLINE AVENUE.
- 3) FINE GRADING OF PARKWAY TO PROVIDE POSITIVE DRAINAGE SHALL BE INCLUDED IN THE COST OF SODDING, SPECIAL.

JJB	JAMES J. BENES & ASSOCIATES, INC.			
	950 Warrenville Road, Suite 101, Lisle, Illinois 60532 Tel. (630) 719-7570 • Fax (630) 719-7589			
F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1504	09-00090-00-SW	COOK	25	9
CONTRACT NO. 63596				ILLINOIS FED. AID PROJECT

FILE NAME =	USER NAME =	DESIGNED — BDH	REVISED —
		DRAWN — SMP	REVISED —
		CHECKED — BDH	REVISED —
		DATE — 02-09-11	REVISED —

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**GEOMETRIC PLAN
CAROLINE AVENUE**

SCALE: NONE SHEET NO. 9 OF 25 SHEETS STA. 60+00 TO STA. 68+00