


SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	FEE
				70% FED 30% VILLAGE 0005	PARKING 100% VILLAGE 0005
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	465	465	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	1,395	1,395	
25200200	SUPPLEMENTAL WATERING	UNIT	14	14	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19	15	4
40600300	AGGREGATE (PRIME COAT)	TON	61	55	6
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	28	28	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,016	908	108
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	177	177	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	1,283	1,110	173
42001300	PROTECTIVE COAT	SQ YD	515	515	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	60	60	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,440	1,440	
42400800	DETECTABLE WARNINGS	SQ FT	176	176	
44000162	HOT-MIX ASHALT SURFACE REMOVAL, 3 1/4"	SQ YD	13,543	12,081	1,462
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	71	71	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,328	1,328	
44000600	SIDEWALK REMOVAL	SQ FT	1,440	1,440	
44201701	CLASS D PATCHES, TYPE I, 5 INCH	SQ YD	40	40	
44201705	CLASS D PATCHES, TYPE II, 5 INCH	SQ YD	125	125	
44201709	CLASS D PATCHES, TYPE III, 5 INCH	SQ YD	210	210	
44201711	CLASS D PATCHES, TYPE IV, 5 INCH	SQ YD	530	530	
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	15	15	
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	50	50	
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	80	80	
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	200	200	
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	5	5	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	15	15	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	25	25	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	30	30	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	2,000	2,000	
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3	3	

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	FEE
				70% FED 30% VILLAGE 0005	PARKING 100% VILLAGE 0005
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1	
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	9	9	
60404950	FRAMES AND GRATES, TYPE 24	EACH	1	1	
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	3	3	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	21	14	7
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,328	1,328	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2,060	2,060	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	129.4	129.4	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3,946	3,946	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	241	241	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	64	64	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	846	846	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	175	175	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	900	900	
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	SQ FT	129.4	129.4	
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3,749	2,323	1,426
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	241	241	
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	64	64	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	846	846	
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	175	175	
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	197	197	
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	465	465	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	
Z0066500	STABILIZED DRIVEWAYS 7"	SQ YD	11	11	
XX003313	REMOVE AND REINSTALL BRICK PAVER	SQ FT	44	44	
X0321809	PERMANENT GROUND ANCHOR	EACH	64		64
X2520700	SODDING, SPECIAL	SQ YD	600	600	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	24	17	7


LEGEND
 - DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME =	DESIGNED -- BDH	REVISED --
		DRAWN -- SMP	REVISED --
	PLOT SCALE =	CHECKED -- BDH	REVISED --
	PLOT DATE =	DATE -- 03/01/2011	REVISED --

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
HILLGROVE AVENUE

SCALE: NONE SHEET NO. 3 OF 17 SHEETS STA. _____ TO STA. _____

 JAMES J. BENES & ASSOCIATES, INC. 950 Warrenville Road, Suite 101, Lisle, Illinois 60532 Tel. (630) 719-7570 • Fax (630) 719-7589				
F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3782	10-00093-00-RS	COOK	17	3
CONTRACT NO. 63600				
ILLINOIS FED. AID PROJECT				