

SUMMARY OF QUANTITIES

ITEM #	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	80% FED./20% STATE					BAUER ROAD 80% Federal 10% State 10% County	0021 OLD RIVER RD 80% Federal 20% State	LATHAM ROAD 80% Federal 10% State 10% County
				0003 ROADWAY	0003 DETOUR ROUTE	0008 MUD CREEK BRIDGE SN 101-0177 AND SN 101-0178	0040 80% FED./20% STATE BOX CULVERTS	0002 (10%) 100% STATE BOX CULVERTS TO BE CLEANED			
X0327307	SLOPED METAL END SECTION WITH GRATE, 57"x38"	EACH	2								
X0327309	SLOPED METAL END SECTION WITH GRATE, 49" x 35"	EACH	2								
X2000310	QUARRY RUN GRANULAR EMBANKMENT	CU YD	74,857	74,857							
X5422205	REINFORCED CONCRETE PIPE TEE, EQUIVALENT ROUND-SIZE, 30" PIPE WITH 24" RISER	EACH	2	2							
X5422205	REINFORCED CONCRETE PIPE WYE, EQUIVALENT ROUND-SIZE, 48" PIPE WITH 24" RISER	EACH	1	1							
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,086	1,086							
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,563	1,563							
20100500	TREE REMOVAL, ACRES	ACRE	25.75	25.75							
20101000	TEMPORARY FENCE	FOOT	482	482							
20101100	TREE TRUNK PROTECTION	EACH	100	100							
20200100	EARTH EXCAVATION	CU YD	640,431	640,431							
20200200	ROCK EXCAVATION	CU YD	4,463	4,463							
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	68,617	68,617							
20800150	TRENCH BACKFILL	CU YD	296	296							
21001000	GEO TECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	12,696	12,696							
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	307,649	307,649							
* 21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	107,739	107,739							
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	400	400							
* 25000100	SEEDING, CLASS 1	ACRE	8.75	8.75							
* 25000210	SEEDING, CLASS 2A	ACRE	20.00	20.00							
* 25000310	SEEDING, CLASS 4	ACRE	19.00	19.00							
* 25000312	SEEDING, CLASS AA	ACRE	75.00	75.00							
* 25000314	SEEDING, CLASS 4B	ACRE	2.00	2.00							
* 25000320	SEEDING, CLASS 5	ACRE	75.00	75.00							
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7,718	7,718							
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7,718	7,718							
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7,718	7,718							
*** 25000750	MOWING	ACRE	66.75	66.75							
* 25100115	MULCH, METHOD 2	ACRE	85.75	85.75							
* 25400200	SELECTIVE MOWING STAKES	EACH	500	500							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	60,025	60,025							
28000305	TEMPORARY DITCH CHECKS	FOOT	2,288	2,288							
28000315	AGGREGATE DITCH CHECKS	TON	109	109							
28000400	PERIMETER EROSION BARRIER	FOOT	22,218	22,218							
28000500	INLET AND PIPE PROTECTION	EACH	103	103							
28100107	STONE RIPRAP, CLASS A4	SQ YD	3,265	3,265							
28100109	STONE RIPRAP, CLASS A5	SQ YD	5,119	3,044			2,075				
28100111	STONE RIPRAP, CLASS A6	SQ YD	84	84							
28200200	FILTER FABRIC	SQ YD	8,468	6,393			2,075				
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	126,477	126,477							
31200100	STABILIZED SUBBASE 4"	SQ YD	1,955	1,955							
35100100	AGGREGATE BASE COURSE, TYPE A	TON	48,916	48,916							
35101400	AGGREGATE BASE COURSE, TYPE B	TON	3,923	3,923							

*** 100% STATE
* Specialty Items

Rev. 6-6-11

USER NAME = thompard	DESIGNED RDT/GC	REVISED -
PLOT SCALE = 50,000 FT / IN.	DRAWN RDT	REVISED -
PLOT DATE = 2/3/2011	CHECKED GC	REVISED -
	DATE 01-14-11	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ILLINOIS ROUTE 2 SUMMARY OF QUANTITIES - 1			
SCALE: N.T.S.	SHEET NO. 6 OF 530 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	77-2-2 & 77-2B-1	WINNEBAGO	530	6
CONTRACT NO. 64813				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				