

SUMMARY OF QUANTITIES				80% FED./20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE
				ROADWAY 0005
20101700	SUPPLEMENTAL WATERING	UNIT	1	1
20400800	FURNISHED EXCAVATION	CU YD	26	26
25200110	SODDING, SALT TOLERANT	SQ YD	62	62
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2701	2701
40600300	AGGREGATE (PRIME COAT)	TON	68	68
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17	17
40600525	LEVELING BINDER (HAND METHOD), N50	TON	16	16
40600990	TEMPORARY RAMP	SQ YD	354	354
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1304	1304
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2608	2608
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	288	288
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	581.5	581.5
42400800	DETECTABLE WARNINGS	SQ FT	290	290
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	31053	31053
44000600	SIDEWALK REMOVAL	SQ FT	938.5	938.5
48101200	AGGREGATE SHOULDERS, TYPE B	TON	647	647
60255500	MANHOLES TO BE ADJUSTED	EACH	4	4
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	1	1
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1494.3	1494.3
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	140.6	140.6
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16729	16729
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1671	1671
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1262	1262
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	619	619
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	93	93
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4659.3	4659.3
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	140.6	140.6

SUMMARY OF QUANTITIES				80% FED./20% STATE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE
				ROADWAY 0005
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16729	16729
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1671	1671
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1262	1262
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	619	619
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	93	93
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	147	147
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	88	88
X4240420	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	SQ FT	527	527
X4400500	COMBINATION CURB AND GUTTER REMOVAL (SPECIAL)	FOOT	48	48
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	2708	2708
X4404700	SIDEWALK REMOVAL (SPECIAL)	SQ FT	106	106
X6061700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B,(SPECIAL)	FOOT	48	48

\*SPECIALTY ITEMS

Rev.