

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				STATE FUNDS	
				100% STATE	STRUCTURE
				0014	RURAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	129		129
40603335	HOT-MIX ASPHALT SURFACE CSE, MIX D, N50	TON	211		211
44000155	HOT-MIX ASPHALT SURFACE REMOVAL 1 1/2"	SO YD	1607		1607
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	56		56
50102400	CONCRETE REMOVAL	CU YD	27.1		27.1
50300255	CONCRETE SUPERSTRUCTURE	CU YD	27		27
50300300	PROTECTIVE COAT	SO YD	181		181
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	4490		4490
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	4010		4010
50800515	BAR SPLICERS	EACH	48		48
52000110	PREFORMED JOINT STRIP SEAL	FOOT	188		188
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	14		14
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	14		14
52100520	ANCHOR BOLTS 1"	EACH	56		56
58100200	WATERPROOFING MEMBRANE SYSTEM	SO YD	960		960
60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	56		56
67100100	MOBILIZATION	L SUM	1		1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1230		1230
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1230		1230
78005110	EPOXY PAVEMENT MARKING, LINE 4"	FOOT	2132		2132
78005130	EPOXY PAVEMENT MARKING, LINE 6"	FOOT	800		800
78300100	PAVEMENT MARKING REMOVAL	SO FT	2304		2304
X0325598	DRAINAGE SCUPPER DS-12M10	EACH	2		2
70100325	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423	EACH	1		1
Z0021904	SILICONE JOINT SEALER, 1"	FOOT	130		130
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	28		28
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	20		20
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SO YD	960		960
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SO YD	20		20
Z0012750	CONCRETE MEDIAN REPAIR	SO FT	68		68
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5")	SO FT	50		50
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5")	SQ FT	68		68
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2		2

*SPECIALTY ITEMS

FILE NAME =	USER NAME = woodshankr1	DESIGNED - RLW	REVISED -
ca:\pwr\work\pwidot\woodshankr1\d0257398\366937-details.dgn		DRAWN - RLW	REVISED -
PLOT SCALE = 1/8" = 1' / IN.		CHECKED -	REVISED -
PLOT DATE = Apr 08, 2011 - 01:05:18 PM		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

Rev. 6-7-11 Rev.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
68	16B-111	LASALLE	20	3
			CONTRACT NO. 66937	
ILLINOIS FED. AID PROJECT				