



* EXISTING INLETS ARE TO REMAIN IN PLACE.
 IF THE INLETS ARE DAMAGED DUE TO THE CONTRACTORS REMOVAL OPERATIONS, THEY SHALL BE REPAIRED OR REPLACED AT THE CONTRACTOR'S EXPENSE.

PLAN

- HMA SURFACE REMOVAL 1 1/2" BITUMINOUS PRIME COAT HMA SURFACE CSE. MIX D, N50
- REMOVE AND REPLACE CURB & GUTTER

FILE NAME =	USER NAME = pateluj	DESIGNED - RLW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ROADWAY PLAN DETAILS	F.A.P. RITE. 68	SECTION 16B-111	COUNTY LASALLE	TOTAL SHEETS 20	SHEET NO. 8
c:\pr_work\p\idot\pateluj\0257398\036637-details.dgn	PLOT SCALE = 1/8" = 100.0000' / 1" / 100'	DRAWN - RLW	REVISED -	SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT		CONTRACT NO. 66937		
PLOT DATE = 5/19/2011	CHECKED -	DATE -	REVISED -							