

**GENERAL NOTES**

THE ENGINEER WILL BE THE SOLE JUDGE CONCERNING CURING TIME FOR THE VARIOUS MICROSURFACING LIFTS.

THE FOLLOWING RATES OF APPLICATION HAVE BEEN USED IN CALCULATING PLAN QUANTITIES:

BITUMINOUS MATERIALS (PRIME CT)	0.08	GAL / SQ YD
SHORT TERM PAVEMENT MARKING	10	FT /100 FT OF APPLICATION
MIX FOR CRACKS, JTS & FLGWYS	0.00283	TONS / SQ YD
MICROSURFACING SINGLE PASS	20	LBS /SQ YD

THE CONTRACTOR SHALL CONTACT JULIE AT LEAST 48 HOURS PRIOR TO EXCAVATION TO DETERMINE WHICH UTILITIES ARE IN THE AREA.

*THE TEMPORARY PAVEMENT MARKING SHALL BE PLACED PRIOR TO MICRO-SURFACING.*

SUMMARY OF QUANTITIES			100% STATE
CODE NO.	ITEM	UNIT	CONSTR. CODE 0005 TOTAL
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1421
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	50
67100100	MOBILIZATION	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7992
70300240	TEMPORARY PAVEMENT MARKING, LINE 6"	FOOT	20000
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2638
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	40000
78300100	PAVEMENT MARKING REMOVAL	SQ FT	10000
78300200	RAISED REFLECTIVE PAVEMENT MARKING REMOVAL	EACH	2000
X0326867	RADAR SPEED TRAILER	CAL MO	1
X0326880	MESSAGE BOARD VEHICLE DRIVER	HOUR	160
X0326907	PORTABLE VEHICLE MOUNTED CHANGEABLE MESSAGE SIGN	CAL MO	1
X7010805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401 (SPECIAL)	L SUM	1
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1
Z0063804	MICRO-SURFACING, SINGLE PASS, TYPE II, MIXTURE D	SQ YD	17760

• SPECIALTY ITEMS

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
DISTRICT THREE

PREPARED BY: David E. Baniak  
DISTRICT STUDIES & PLANS ENGINEER

DATE: MARCH 30, 2011

EXAMINED BY: [Signature]  
DISTRICT CONSTRUCTION ENGINEER

[Signature]  
DISTRICT MATERIALS ENGINEER

[Signature]  
DISTRICT OPERATIONS ENGINEER

FILE NAME =	USER NAME = carpenterdj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTES AND SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\psidot\carpenterdj\0253636\036817-sht-cover.dgn		DRAWN -	REVISED -			80	(50-2,3,4,5)-2	LASALLE	6	2	
PLOT SCALE = 50,0000' / IN.		CHECKED -	REVISED -			SCALE: _____ SHEET NO. ___ OF ___ SHEETS STA. _____ TO STA. _____					
PLOT DATE = Mar 30, 2011 - 07:33:00 AM		DATE -	REVISED -			ILLINOIS FED. AID PROJECT					