



FRAMING PLAN SPAN 16
Eastbound Lanes

BILL OF MATERIAL

Item	Unit	Quantity
Hot-Mix Asphalt Wearing Surface Removal, Deck	Sq. Yc.	643
Bridge Deck Scarification, 3/4"	Sq. Yc.	643
Bridge Deck Latex Concrete Overlay, 2 1/4"	Sq. Yc.	633
Plug Existing Deck Drains	Each	10
Floor Drain Extension	Each	10
Structural Steel Repair	Pound	940
Bolt Replacement	Each	1
Deck Slab Repair (Full Depth, Type II)	Sq. Yc.	0.6

LEGEND

- ① Plug Existing Floor Drains
- ② Extend Existing Drain
- Ⓐ Finger Plate Expansion Joint Replacement

FILE NAME =	USER NAME = #USER#	DESIGNED - JAN	REVISED -
#FILEL#		CHECKED - BTO	REVISED -
	PLOT SCALE = #SCALE#	DRAWN - MJK	REVISED -
	PLOT DATE = #DATE#	CHECKED - JAN	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

GENERAL PLAN & REPAIR LOCATION
EASTBOUND SPAN 16 S.N. 090-0108

SHEET NO. 26 OF 65 SHEETS

F.A.I. RTE.:	SECTION:	COUNT:	TOTAL SHEETS:	SHEET NO.:
474		PEORIA & T. ZEWELL	129	60
			CONTRACT NO. 68069	
ILLINOIS FED. AID PRG. CT				