

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY				RETAINING WALL
				80% FED 20% STATE		100% STATE		80% FED 20% STATE
				FULTON	MCDONOUGH	FULTON	MCDONOUGH	FULTON
				CONSTRUCTION TYPE CODE				
			0005	0005	0005	0005	0040	
20100500	TREE REMOVAL, ACRES	ACRE	3.5	3.5				
20200100	EARTH EXCAVATION	CU YD	26,122	21,708	4,414			
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	36	36				
20800150	TRENCH BACKFILL	CU YD	225	225				
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	67	67				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	41,893	35,994	5899			
* 21400100	GRADING AND SHAPING DITCHES	FOOT	5,942	5,942				
25000210	SEEDING, CLASS 2A	ACRE	8.7	7.4	1.3			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	779	666	113			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	779	666	113			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	779	666	113			
25100115	MULCH, METHOD 2	ACRE	16.9	14.2	2.7			
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	5,569	3,880	1,689			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,473	2,332	141			
28000305	TEMPORARY DITCH CHECKS	FOOT	1,584	1,320	264			
28000400	PERIMETER EROSION BARRIER	FOOT	2,052	1,689	363			
28000500	INLET AND PIPE PROTECTION	EACH	25	20	5			
28100105	STONE RIPRAP, CLASS A3	SQ YD	20	11	9			
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,965	1,888	77			
28100109	STONE RIPRAP, CLASS A5	SQ YD	637	637				
28100125	STONE RIPRAP, CLASS B3	SQ YD	4,463	3,851	612			
28200200	FILTER FABRIC	SQ YD	2,624	2,546	78			