

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY				RETAINING WALL
				80% FED 20% STATE		100% STATE		80% FED 20% STATE
				FULTON	MCDONOUGH	FULTON	MCDONOUGH	FULTON
				CONSTRUCTION TYPE CODE				
			0005	0005	0005	0005	0040	
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	1,044	1,044				
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	484	484				
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	1,555	1,386	169			
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	48.1	42.3	5.8			
40600300	AGGREGATE (PRIME COAT)	TON	355	322	33			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,044	697	347			
40600990	TEMPORARY RAMP	SQ YD	199	141	58			
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	10,009	9,036	973			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	409	376	33			
44000100	PAVEMENT REMOVAL	SQ YD	77	77				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	113,943	103,240	10,703			
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	592	534	58			
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	38	38				
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	2,011	1,238	773			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	38,825	38,825				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,759	3,171	588			
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	3,242	3,242				
* 50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	1				
* 50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	1				
* 50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	1				
* 50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	1				