

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY				RETAINING WALL
				80% FED 20% STATE		100% STATE		80% FED 20% STATE
				FULTON	MCDONOUGH	FULTON	MCDONOUGH	FULTON
				CONSTRUCTION TYPE CODE				
			0005	0005	0005	0005	0040	
50102400	CONCRETE REMOVAL	CU YD	11	11				
* 50104400	CONCRETE HEADWALL REMOVAL	EACH	82	75	7			
* 50105220	PIPE CULVERT REMOVAL	FOOT	1,960	1,813	147			
50200100	STRUCTURE EXCAVATION	CU YD	288				288	
50300225	CONCRETE STRUCTURES	CU YD	139.5				139.5	
50300300	PROTECTIVE COAT	SQ YD	464				464	
50500505	STUD SHEAR CONNECTORS	EACH	624				624	
50800105	REINFORCEMENT BARS	POUND	17,495	17,370	125			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	18,535	935			17,600	
51500100	NAME PLATES	EACH	1				1	
54002020	EXPANSION BOLTS 3/4 INCH	EACH	138	114	24			
54003000	CONCRETE BOX CULVERTS	CU YD	130	130				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2		2			
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	6	6				
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	10	7	3			
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	5	5				
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1		1			
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	1	1				
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	8	8				
54214512	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 27"	EACH	2	2				
* 54215550	METAL END SECTIONS 15"	EACH	14	12	2			

FILE NAME = sht-500.dgn	USER NAME = crespole	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 / / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/11/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.P. RTE. 685	SECTION **	COUNTY *	TOTAL SHEETS 329	SHEET NO. 9
CONTRACT NO. 68599			ILLINOIS FED. AID PROJECT	