

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY				RETAINING WALL
				80% FED 20% STATE		100% STATE		80% FED 20% STATE
				FULTON	MCDONOUGH	FULTON	MCDONOUGH	FULTON
				CONSTRUCTION TYPE CODE				
			0005	0005	0005	0005	0040	
70106700	TEMPORARY RUMBLE STRIP	EACH	12	12				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14,292	12,901	1,391			
70300220	TEMPORARY PAVEMENT MARKING- LINE 4"	FOOT	114,667	104,160	10,507			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,179	1,064	115			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,220	1,220				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,060	1,060				
* 78001110	PAINT PAVEMENT MARKING- LINE 4"	FOOT	107,033	96,526	10,507			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	511	460	51			
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	23	21	2			
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	14	12	2			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2,545	2,545				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	200	180	20			
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	10,695					10,695
X2503100	MOWING	UNIT	785			706	79	
X3112700	COARSE AGGREGATE FILL	TON	118	118				
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1/2" - 4.75, N50	TON	5,005	4,519	486			
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	624	624				
X4402720	GUTTER REMOVAL (SPECIAL)	FOOT	1,500	1,500				
X6062700	CONCRETE GUTTER, TYPE A (SPECIAL)	FOOT	1,416	1,416				
X6640535	CHAIN LINK FENCE, 6' ATTACHED TO STRUCTURE	FOOT	400					400
X6650202	WOVEN WIRE FENCE REMOVAL	FOOT	3,209	3,209				

* SPECIALTY ITEM