

RESURFACING SCHEDULE

LOCATION	TOTAL ROADWAY WIDTH (FT)	LENGTH (FT)	AREA (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT (SQ YD)	TEMPORARY RAMP (SQ YD)	HOT-MIX ASPHALT SURFACE REMOVAL 1.5 IN (SQ YD)	* POLYMERIZED BITUMINOUS MATERIALS PRIME COAT (TON)	AGGREGATE (PRIME COAT) (TON)	POLYMERIZED LEVELING BINDER (MM) 0.75 IN (TON)	INCIDENTAL HOT-MIX ASPHALT SURFACING (TON)	HOT-MIX ASPHALT SURFACE CSE MIX D, NS0, 1.5 IN (TON)
STA. 202 + 91 TO 203 + 21	26.00	30.00	86.67	86.67	14.44		0.05	0.26	3.64		7.28
STA. 203 + 21 TO 300 + 00	26.00	9,679.00	27,961.56			27,961.56	14.54	83.88	1,174.39		2,348.77
STA. 300 + 00 TO 304 + 00	26.00	400.00	1,155.56			1,155.56	0.66	3.93	48.53		97.07
STA. 304 + 00 TO 317 + 90	26.00	1,390.00	4,015.56			4,015.56	2.09	12.05	168.65		337.31
STA. 317 + 90 TO 327 + 48	26.00	958.13	2,767.93			2,767.93	1.57	9.37	116.25		232.51
STA. EQ 327+48(BK) = 327+30(AH)											
STA. 327 + 30 TO 328 + 98	26.00	167.96	485.22			485.22	0.27	1.64	20.38		40.76
STA. 328 + 98 TO 368 + 96	26.00	3,998.00	11,549.78			11,549.78	6.01	34.65	485.09		970.18
STA. 368 + 96 TO 380 + 12	26.00	1,116.00	3,224.00			3,224.00	1.83	10.91	135.41		270.82
STA. 378 + 62 TO 410 + 75	26.00	3,212.72	9,281.19			9,281.19	4.83	27.84	389.81		779.62
STA. 410 + 75 TO 411 + 00	24.00	25.00	66.67			50.00	0.04	0.21	2.80		5.60
STA. 411 + 00 TO 422 + 68	24.00	1,168.26	3,115.36			3,115.36	1.71	10.12	130.85		261.69
STA. 422 + 68 TO 423 + 00	24.00	31.75	84.67			63.50	0.05	0.26	3.56		7.11
STA. 423 + 00 TO 557 + 20	26.00	13,420.00	38,768.89			38,768.89	20.16	116.31	1,628.29		3,256.59
STA. 557 + 20 TO 557 + 50	26.00	30.00	86.67	86.67	14.44		0.05	0.26	3.64		7.28
OMISSION STA 557+50 TO STA 588+70											
STA. 588 + 70 TO 589 + 00	26.00	30.00	86.67	86.67	14.44		0.05	0.26	3.64		7.28
STA. 589 + 00 TO 607 + 72	26.00	1,872.00	5,408.00			5,408.00	2.81	16.22	227.14		454.27
STA. EQ 607+72(BK) = 607+92(AH)											
STA. 607 + 92 TO 617 + 12	26.00	920.00	2,657.78			2,657.78	1.38	7.97	111.63		223.25
STA. EQ 617+12(BK) = 616+60(AH)											
STA. 616 + 60 TO 622 + 76	26.00	616.00	1,779.56			1,779.56	0.93	5.34	74.74		149.48
STA. 622 + 76 TO 623 + 06	26.00	30.00	86.67	86.67	14.44		0.05	0.26	3.64		7.28
IL-41											
STA. 207 + 00 TO 207 + 30	26.00	30.00	86.67	86.67	14.44		0.05	0.26	3.64		7.28
STA. 207 + 30 TO 209 + 07	26.00	177.00	511.33			511.33	0.27	1.53	21.48		42.95
STA. 207 + 00 TO 207 + 30	26.00	30.00	86.67	86.67	14.44		0.05	0.26	3.64		7.28
STA. 207 + 30 TO 208 + 50	26.00	119.84	346.20			346.20	0.18	1.04	14.54		29.08
SIDE ROADS											
RIGDON RD (S)		15.00	52.28				0.03	0.16		6.59	
RIGDON RD (N)		26.00	83.01	54.82	11.39	28.19	0.04	0.25		10.46	
COX RD		19.00	59.08				0.03	0.18		7.44	
CH 15		62.00	200.51	43.44	10.72	157.08	0.10	0.60		25.26	
IL 9 & CH 15		60.00	135.83	45.85	11.11	89.99	0.07	0.41		17.12	
SWEENEYS RD (N)		86.00	170.74	31.96	7.94	139.11	0.09	0.51		21.51	
SWEENEYS RD (E)		66.00	151.65	39.29	10.00	112.36	0.08	0.45		19.11	
FREDERICK RD		30.00	120.82	60.94	12.22	59.89	0.06	0.36		15.22	
BUCHEN RD		27.00	104.11	58.31	10.83	45.80	0.05	0.31		13.12	
SEVEN HILLS (S)		29.00	94.66	48.18	10.00	46.49	0.05	0.28		11.93	
SEVEN HILLS (N)		29.00	155.29	91.38	16.39	63.91	0.08	0.47		19.57	
MANLEY RD (S)		30.00	120.91				0.06	0.36		15.24	
MANLEY RD (N)		32.00	112.08	49.70	11.39	59.05	0.06	0.34		14.12	
ENTRANCES & TURNOUTS											
PRIVATE ENTRANCES			436.62				0.23	1.31		55.01	
COMERCIAL ENTRANCES			135.78				0.07	0.41		17.11	
FIELD ENTRANCES			724.47				0.38	2.17		91.28	
ENTRANCE+MAILBOX TURNOUT			316.24				0.16	0.95		39.85	
MAILBOX TURNOUT			74.93				0.04	0.22		9.44	
TOTALS				1,044	199	113,943	61	355	4,775	409	9,551
								SAFETY EDGE (4.8%)	229		458
								TOTALS	5,005		10,009

* See Project Specific Notes

FILE NAME = sht-schedule.dgn
 USER NAME = crespole
 PLOT SCALE = 100.0000' / IN.
 PLOT DATE = 4/7/2011

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 685	SECTION **	COUNTY *	TOTAL SHEETS 329	SHEET NO. 17
ILLINOIS FED. AID PROJECT			CONTRACT NO. 68599	