

CLASS D PATCHES, 14 INCH			
LOCATION FROM TO	44201815 TYPE II (SQ YD)	44201819 TYPE III (SQ YD)	44201821 TYPE IV (SQ YD)
TWO MILES WEST OF SPOON RIVER TO RIGDON RD	11.56		
RIGDON RD TO COX RD	101.11	17.33	86.67
COX RD TO FIRST CURVE			28.89
FIRST CURVE TO SECOND CURVE	95.33		216.67
SECOND CURVE TO FREDRICK RD	28.89		57.78
FREDRICK RD TO BUCHEN RD			173.33
BUCHEN RD TO SEVEN HILLS	49.11		
SEVEN HILLS TO MANLEY RD	196.44		223.89
MANLEY RD TO OMISSION	36.89		404.44
OMISSION TO IL-41 WYE	28.89		585.00
IL-41 WYE TO END	28.89		187.78
STA 302+10 TO STA 302+26			46.22
STA 423+56 TO STA 423+63		20.22	
STA 555+83 TO STA 555+88	14.44		
TOTAL	592	38	2,011

TEMPORARY SEEDING SCHEDULE						
LOCATION STATION TO STATION			LT/RT	PLAN AREA (SQ FT)	25100115 MULCH, METHOD 2 (ACRE)	28000250 TEMPORARY EROSION CONTROL SEEDING (100 LB/ACRE) (POUND)
217+00.00 TO 221+75.00	RT	3,412.75	0.0783	7.83		
237+00.00 TO 242+50.00	LT	6,656.90	0.1528	15.28		
237+00.00 TO 242+50.00	RT	11,915.00	0.2735	27.35		
299+50.00 TO 304+00.00	LT	11,183.50	0.2567	25.67		
299+50.00 TO 304+50.00	RT	13,239.00	0.3039	30.39		
317+00.00 TO 329+00.00	LT	6,579.30	0.1510	15.10		
317+00.00 TO 329+00.00	RT	8,510.88	0.1954	19.54		
368+50.00 TO 381+00.00	LT	4,218.80	0.0969	9.69		
368+50.00 TO 381+00.00	RT	3,580.75	0.0822	8.22		
407+50.00 TO 425+00.00	LT	52,217.00	1.1987	119.87		
407+50.00 TO 425+50.00	RT	41,756.00	0.9586	95.86		
430+50.00 TO 434+50.00	RT	5,157.00	0.1184	11.84		
430+50.00 TO 434+50.00	LT	5,189.30	0.1191	11.91		
446+50.00 TO 450+00.00	RT	6,327.00	0.1452	14.52		
445+82.00 TO 450+00.00	LT	9,448.90	0.2169	21.69		
533+50.00 TO 548+00.00	RT	50,926.40	1.1691	116.91		
530+50.00 TO 547+50.00	LT	51,671.00	1.1862	118.62		
554+00.00 TO 557+50.00	LT	3,803.30	0.0873	8.73		
555+00.00 TO 557+50.00	RT	2,062.47	0.0473	4.73		
590+00.00 TO 601+50.00	RT	26,162.50	0.6006	60.06		
590+00.00 TO 602+50.00	LT	31,769.00	0.7293	72.93		
621+50.00 TO 623+00.00	LT	2,004.10	0.0460	4.60		
621+50.00 TO 623+00.00	RT	1,316.13	0.0302	3.02		
SUB-TOTALS					8.24	824
TOTAL					8.24	2,473

NOTE: 3 APPLICATIONS OF TEMPORARY SEEDING

REMOVAL OF EXISTING STRUCTURES						
LOCATION	LT/RT	DESCRIPTION	50100300	50100400	50100500	50100600
			NO. 1	NO. 2	NO. 3	NO. 4
			EACH	EACH	EACH	EACH
STA. 302+17.76		3'x3' box	1			
STA. 423+59.29		2'x2' Box		1		
STA. 447+89.94	RT	Drop Box			1	
STA. 555+85.09		2'x2' Box				1
TOTALS			1	1	1	1

HOT-MIX ASPHALT SHOULDERS 8"						
LOCATION STATION TO STATION			LT/RT	LENGTH FOOT	WIDTH FOOT	48203029 SQ YD
299+40.00 TO 304+08.00	RT	468.0	5.0	260.0		
300+27.00 TO 303+72.00	LT	345.0	5.0	191.7		
317+90.00 TO 327+48.00	LT&RT	1,916.0	4.0	851.6		
STA. EQ: STA 327+48.13 (BK) = STA 327+30.04 (AH)						
327+30.00 TO 328+98.00	LT&RT	336.0	4.0	149.3		
368+96.00 TO 380+12.00	LT&RT	2,232.0	4.0	992.0		
410+75.00 TO 422+68.26	LT	1,193.3	3.0	397.8		
411+00.00 TO 423+00.00	RT	1,200.0	3.0	400.0		
TOTAL						3,242

SHOULDER RUMBLE STRIPS				
LOCATION STATION TO STATION		LT/RT	LENGTH FOOT	64200105 FOOT
317+90.00 TO 327+48.00	LT&RT	1,916.0	1,916.0	
STA. EQ: STA 327+48.13 (BK) = STA. 327+30.04				
327+30.00 TO 328+98.00	LT&RT	336.0	336.0	
368+96.00 TO 380+12.00	LT&RT	2,232.0	2,232.0	
TOTAL				4,484

FILE NAME = sht-schedule.dgn	USER NAME = crespole	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/7/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 685	SECTION **	COUNTY *	TOTAL SHEETS 329	SHEET NO. 19
CONTRACT NO. 68599			ILLINOIS FED. AID PROJECT	