

CONCRETE GUTTER, TYPE B				
LOCATION		LT/RT	60602800	
STATION TO STATION			FOOT	
418+88.00	TO	423+03.00	RT	415.00
TOTAL				415.00

CONCRETE GUTTER, TYPE A (SPECIAL)				
LOCATION		LT/RT	X6062700	
STATION TO STATION			FOOT	
410+87.00	TO	415+00.00	LT	413.00
411+12.00	TO	414+50.00	RT	338.00
419+28.00	TO	423+00.00	RT	372.00
419+63.00	TO	422+56.00	LT	293.00
TOTAL				1,416.00

CLASS SI CONCRETE (OULET)				
LOCATION		LT/RT	60600095	
STATION TO STATION			CU YD	
410+75.00	TO	410+87.00	LT	1.20
411+00.00	TO	411+12.00	RT	1.20
414+50.00	TO	415+16.00	RT	7.60
415+00.00	TO	415+56.00	LT	6.50
418+65.00	TO	419+28.00	RT	7.25
419+07.00	TO	419+63.00	LT	6.50
422+56.00	TO	422+68.00	LT	1.20
423+00.00	TO	423+12.00	RT	1.20
TOTAL				32.7

INLET AND PIPE PROTECTION				
LOCATION	LT / RT	OFFSET FOOT	28000500	
			EACH	
STA 239+18.00	LT	27.22	1	
STA 240+17.00	LT	30.65	1	
STA 242+48.00	RT	23.37	1	
STA 302+18.00	LT	45.13	1	
STA 303+99.00	LT	21.4	1	
STA 409+81.00	LT	40.31	1	
STA 423+58.00	RT	26.47	1	
STA 425+05.00	LT	21.23	1	
STA 431+20.00	RT	21.96	1	
STA 432+58.00	LT	33.93	1	
STA 446+08.00	LT	23.18	1	
STA 447+91.00	RT	38.42	1	
STA 448+65.00	LT	39.93	1	
STA 450+29.00	LT	22.74	1	
STA 451+30.00	LT	22.59	1	
STA 536+43.00	LT	37.21	1	
STA 539+64.00	LT	38.95	1	
STA 544+66.00	LT	42.73	1	
STA 546+32.00	LT	28.4	1	
STA 548+22.00	RT	19.24	1	
STA 589+84.00	RT	20.93	1	
STA 590+01.00	LT	21.79	1	
STA 591+93.00	LT	33.25	1	
STA 596+75.00	RT	27.58	1	
STA 599+09.00	LT	37.36	1	
TOTAL			25	

AGGREGATE SHOULDERS, TYPE B							
LOCATION			LT/RT	LENGTH	WIDTH	THICKNESS/	48101200
STATION TO STATION				FT	FT	TYPE	TON
202+91.00	TO	238+00.00	LT&RT	7,018	3	WEDGE	216.44
238+00.00	TO	242+40.00	LT&RT	880	5	6 in	167.04
242+40.00	TO	327+48.13	LT&RT	17,016	3	WEDGE	524.80
STA EQ: STA 327+48.13 (BK) = STA 327+30.04 (AH)							
327+30.04	TO	408+00.00	LT&RT	16,140	3	WEDGE	497.77
408+00.00	TO	411+00.00	LT&RT	600	5	6 in	113.89
411+00.00	TO	423+00.00	LT&RT	2,400	3	WEDGE	74.02
423+00.00	TO	425+00.00	LT&RT	400	5	6 in	75.93
425+00.00	TO	431+50.00	LT&RT	1,300	3	WEDGE	40.09
431+50.00	TO	434+50.00	LT&RT	600	5	6 in	113.89
434+50.00	TO	446+50.00	LT&RT	2,400	3	WEDGE	74.02
446+50.00	TO	449+55.00	LT&RT	610	5	6 in	115.79
449+55.00	TO	531+00.00	LT	8,145	3	WEDGE	251.20
449+55.00	TO	533+50.00	RT	8,395	3	WEDGE	258.91
531+00.00	TO	547+50.00	LT	1,650	5	6 in	313.19
533+50.00	TO	547+50.00	RT	1,400	5	6 in	265.74
547+50.00	TO	558+50.00	LT&RT	2,200	3	WEDGE	67.85
OMISSION: STA 558+50 TO STA 588+70							
588+70.00	TO	590+50.00	LT&RT	360	3	WEDGE	11.10
590+50.00	TO	601+17.00	RT	1,067	5	6 in	202.53
590+50.00	TO	602+00.00	LT	1,150	5	6 in	218.29
601+17.00	TO	607+71.98	RT	655	3	WEDGE	20.20
602+00.00	TO	607+71.98	LT	572	3	WEDGE	17.64
STA. EQ: STA 607+71.98(BK) = STA 607+92.41(AH)							
607+92.41	TO	617+12.19	LT&RT	1,840	3	WEDGE	56.73
STA EQ: STA 617+12.19 (BK) = STA 616+60.02 (AH)							
616+60.02	TO	623+06.00	LT&RT	1,292	3	WEDGE	39.85
WYE (IL 41)							
207+00.00	TO	209+06.68	LT&RT	413	3	WEDGE	12.75
207+00.00	TO	208+49.84	LT&RT	300	3	WEDGE	9.24
TOTAL							3,759

FILE NAME = sht-schedule.dgn	USER NAME = crespole	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 685	SECTION **	COUNTY	TOTAL SHEETS 329	SHEET NO. 22
CONTRACT NO. 68599			ILLINOIS FED. AID PROJECT	