

**DRAINAGE SCHEDULE (SIDE ROADS)**

LOCATION	LT/RT	PIPE CULVERT CL A, TY 1 24" FOOT	PIPE CULVERT CL A, TY 1 EQRS 18" FOOT	PIPE CULVERT CL A, TY 1 EQRS 27" FOOT	PRCF END SECTION 24" EACH	PRCF END SECTION EQRS 18" EACH	PRCF END SECTION EQRS 27" EACH	US ELEV	DS ELEV
RIGDON RD	RT		30			2		623.33	623.20
RIGDON RD	LT		36			2		622.91	622.77
COX RD	LT		32			2		619.89	619.76
CH 15	LT			110			2	623.61	621.96
BUCHEN RD	RT	60			2			633.58	632.41
SEVEN HILLS RD	LT		36			2		639.56	639.42
<b>TOTAL</b>		60	134	110	2	8	2		

**MANHOLES, TYPE A, 5' DIAMETER, TYPE 1 FRAME, CLOSED LID**

LOCATION	LT/RT	OFFSET FOOT	60221100 EACH
STA. 447+91.00	LT	31.78	1
STA. 539+60.00	RT	34.81	1
<b>TOTAL</b>			2

**HOT-MIX ASPHALT BASE COURSE WIDENING, 10"**

LOCATION STATION TO STATION	LT/RT	AREA SQ FT	35600716 SQ YD
410+75.00 TO 414+58.72	LT	1,151.16	127.91
411+00.00 TO 414+57.00	RT	1,071.00	119.00
419+50.00 TO 422+66.00	RT	948.00	105.33
419+50.00 TO 422+68.25	LT	954.75	106.08
556+50.00 TO 557+50.00	RT	116.92	12.99
556+50.00 TO 557+50.00	LT	116.04	12.89
<b>TOTAL</b>			484

**GRATING FOR PRECAST REINFORCED CONCRETE FLARED END SECTION**

LOCATION	LT/RT	54247130	54247150	54247170	54248140
		24 INCH (EACH)	30 INCH (EACH)	36 INCH (EACH)	EQRS 27 INCH (EACH)
240+18.45	LT&RT			2	
423+59.49	LT		1		
432+58.33	LT		1		
432+58.33	RT		1		
555+85.09	LT	1			
555+85.09	RT	1			
591+93.06	LT		1		
622+55.06	LT				
622+55.06	RT				
SIDE ROADS					
CH 15	LT&RT				2
BUCHEN RD	RT	2			
<b>TOTALS</b>		4	4	2	2

**TREE REMOVAL, ACRES**

LOCATION	LT/RT	20100500 ACRE
413+00.00 TO 419+50.00	LT	0.80
415+00.00 TO 419+25.00	RT	0.75
532+00.00 TO 535+00.00	LT	0.36
534+25.00 TO 537+80.00	RT	0.76
538+73.00 TO 547+00.00	RT	0.81
<b>TOTAL</b>		3.5

**PAVEMENT REMOVAL**

LOCATION	LT/RT	AREA (SQ FT)	44000100 SQ YD
RIGDON RD	RT	96.6	10.73
CH 15	LT	427.83	47.54
BUCHEN RD	RT	85.51	9.50
SEVEN HILLS RD	LT	87.16	9.68
<b>TOTAL</b>			77

**SUB BASE GRANULAR MATERIAL, TYPE B, 4"**

LOCATION STATION TO STATION	LT/RT	AREA SQ FT	31101200 SQ YD
300+27.59 TO 303+72.16	LT	2,191.50	243.50
302+17.81		1,167.75	129.75
410+75.00 TO 414+58.72	LT	1,151.19	127.91
411+00.00 TO 414+57.00	RT	1,071.00	119.00
419+50.00 TO 422+66.00	RT	947.97	105.33
419+50.00 TO 422+68.25	LT	954.72	106.08
423+59.49		123.66	13.74
555+85.09		100.80	11.20
556+50.00 TO 557+50.00	RT	116.01	12.89
556+50.00 TO 557+50.00	LT	116.91	12.99
N. RIGDON RD		184.68	20.52
S. RIGDON RD		242.01	26.9
COX RD		187.65	20.9
CH 15 RD		422.55	47.0
BUCHEN RD		219.87	24.4
SEVEN HILLS RD		194.13	21.6
<b>TOTAL</b>			1,044

**GUTTER REMOVAL (SPECIAL)**

LOCATION STATION TO STATION	LT/RT	LENGTH FT	X4402720 FT
411+00.00 TO 415+00.00	LT&RT	400	800.0
419+00.00 TO 422+50.00	LT&RT	350.00	700.0
<b>TOTAL</b>			1,500