

GUARDRAIL REMOVAL				
LOCATION			LT/RT	63200310
STATION TO STATION				FOOT
198+80.00	TO	199+30.00	LT	50.0
202+82.00	TO	203+07.00	LT	25.0
211+57.00	TO	213+07.00	RT	150.0
212+44.00	TO	213+44.00	LT	100.0
217+58.00	TO	219+45.50	RT	187.5
239+57.50	TO	240+20.00	RT	62.5
301+66.00	TO	302+66.00	RT	100.0
301+78.00	TO	302+78.00	LT	100.0
415+02.00	TO	418+77.00	RT	375.0
415+86.50	TO	418+74.00	LT	287.5
422+99.50	TO	424+12.00	LT	112.5
446+74.50	TO	448+37.00	LT	162.5
533+37.50	TO	534+75.00	LT	137.5
533+66.00	TO	537+41.00	RT	375.0
535+96.00	TO	536+96.00	LT	100.0
538+72.50	TO	539+85.00	RT	112.5
539+36.00	TO	540+36.00	LT	100.0
543+27.00	TO	547+02.00	RT	375.0
544+06.00	TO	545+31.00	LT	125.0
555+39.00	TO	556+14.00	RT	75.0
591+37.00	TO	592+37.00	RT	100.0
622+22.00	TO	622+97.00	LT	75.0
EAST WYE (IL 41)				
204+37.00	TO	204+62.00		25.0
207+24.50	TO	207+49.50		25.0
TOTAL				3,337.50

STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS				
LOCATION			LT/RT	63000001
STATION TO STATION				FOOT
211+62.00	TO	212+87.00	RT	125.00
212+55.00	TO	213+42.50	LT	87.50
217+84.00	TO	219+46.50	RT	162.50
300+24.00	TO	303+24.00	RT	300.00
301+11.50	TO	303+11.50	LT	200.00
TOTAL				875.00

GUARDRAIL AGGREGATE EROSION CONTROL					
LOCATION			LT/RT	LENGTH	Z0001002
STATION TO STATION				FOOT	TON
198+70.00	TO	199+30.00	LT	60	12.15
202+82.00	TO	203+66.00	LT	84	14.58
211+03.41	TO	213+71.41	RT	268	54.46
211+71.20	TO	214+01.70	LT	231	41.81
216+98.00	TO	220+37.50	RT	340	46.87
299+40.00	TO	304+08.00	RT	468	85.42
300+27.50	TO	303+72.00	RT	345	64.19
IL 41 EAST WYE					
203+83.00	TO	204+67.00	LT	84	14.58
207+16.00	TO	208+00.00	LT	84	14.58
TOTAL					349

GUARDRAIL MARKERS, TYPE A			
LOCATION		LT/RT	78200410
			EACH
STA.	199+30.00	LT	1
STA.	202+82.00	LT	1
STA.	211+62.00	RT	1
STA.	212+24.50	RT	1
STA.	212+55.00	LT	1
STA.	212+87.00	RT	1
STA.	212+99.00	LT	1
STA.	213+42.50	LT	1
STA.	217+84.00	RT	1
STA.	218+65.00	RT	1
STA.	219+46.00	RT	1
STA.	219+46.50	RT	1
STA.	300+24.00	RT	1
STA.	300+99.00	RT	1
STA.	301+11.50	LT	1
STA.	301+74.00	RT	1
STA.	301+78.50	LT	1
STA.	302+45.50	LT	1
STA.	302+49.00	RT	1
STA.	303+11.50	LT	1
STA.	303+24.00	RT	1
EAST WYE (IL 41)			
STA.	204+62.00	LT	1
STA.	207+24.50	LT	1
TOTAL			23

TERMINAL MARKER - DIRECT APPLIED			
LOCATION		LT/RT	78201000
			EACH
STA.	198+80.00	LT	1
STA.	203+32.00	LT	1
STA.	211+37.00	RT	1
STA.	212+05.00	LT	1
STA.	213+37.00	RT	1
STA.	213+67.50	LT	1
STA.	217+34.00	RT	1
STA.	219+96.50	RT	1
STA.	299+74.00	RT	1
STA.	300+61.50	LT	1
STA.	303+61.50	LT	1
STA.	303+74.00	RT	1
EAST WYE (IL 41)			
STA.	204+12.00	LT	1
STA.	207+74.50	LT	1
TOTAL			14

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)					
LOCATION			LT/RT	LENGTH	63100167
STATION TO STATION				FOOT	EACH
198+80.00	TO	199+30.00	LT	50.00	1
202+82.00	TO	203+32.00	LT	50.00	1
211+12.00	TO	211+62.00	RT	50.00	1
212+05.00	TO	212+55.00	LT	50.00	1
212+87.00	TO	213+37.00	RT	50.00	1
213+42.50	TO	213+92.50	LT	50.00	1
217+34.00	TO	217+84.00	RT	50.00	1
219+46.50	TO	219+96.50	RT	50.00	1
299+74.00	TO	300+24.00	RT	50.00	1
300+61.50	TO	301+11.50	LT	50.00	1
303+11.50	TO	303+61.50	LT	50.00	1
303+24.00	TO	303+74.00	RT	50.00	1
EAST WYE (IL 41)					
204+12.00	TO	204+62.00	RT	50.00	1
207+24.50	TO	207+74.50	RT	50.00	1
TOTAL					14

PERMANENT SURVEY MARKERS, TYPE I & PERMANENT SURVEY TIES			
LOCATION		66700205	X6670109
		EACH	EACH
STA.	217+08.48	1	4
STA.	243+71.04	1	4
STA.	270+68.91	1	4
STA.	297+58.98	1	4
STA.	349+05.57	1	4
STA.	399+98.33	1	4
STA.	426+50.04	1	4
STA.	452+94.43	1	4
STA.	479+63.21	1	4
STA.	506+30.57	1	4
STA.	532+96.48	1	4
RETAINING WALL		1	
TOTALS		12	44

FILE NAME = sht-schedule.dgn	USER NAME = crespole	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. R.T.E. 685	SECTION **	COUNTY *	TOTAL SHEETS 329	SHEET NO. 32
			CONTRACT NO. 68599	

ILLINOIS FED. AID PROJECT * Fulton, McDonough