

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY I-74 RURAL 90% FEDERAL 10% STATE 0021
20200100	EARTH EXCAVATION	CU YD	1670
20400800	FURNISHED EXCAVATION	CU YD	7250
20800150	TRENCH BACKFILL	CU YD	36
25000210	SEEDING, CLASS 2A	ACRE	7.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	675
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	675
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	675
25100115	MULCH, METHOD 2	ACRE	7.5
25100630	EROSION CONTROL BLANKET	SQ YD	28
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	750
28000305	TEMPORARY DITCH CHECKS	FOOT	3024
28000500	INLET AND PIPE PROTECTION	EACH	31
28100201	STONE RIPRAP, CLASS A1	TON	79
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	215
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	57
44004000	PAVED DITCH REMOVAL	FOOT	3838
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2247
50104400	CONCRETE HEADWALL REMOVAL	EACH	63
50105220	PIPE CULVERT REMOVAL	FOOT	81
54244405	FLUSH INLET BOX FOR MEDIAN, STANDARD 542546	EACH	20
54246405	INLET BOX, STANDARD 542531	EACH	6
54248510	CONCRETE COLLAR	CU YD	9
550A0050	STORM SEWERS, CLASS A, TYPE I 12"	FOOT	1943
550A0090	STORM SEWERS, CLASS A, TYPE I 18"	FOOT	1467
550A0120	STORM SEWERS, CLASS A, TYPE I 24"	FOOT	267
550A0140	STORM SEWERS, CLASS A, TYPE I 30"	FOOT	6
550A0160	STORM SEWERS, CLASS A, TYPE I 36"	FOOT	9
55101200	STORM SEWER REMOVAL 24"	FOOT	50
55101400	STORM SEWER REMOVAL 30"	FOOT	7
55101600	STORM SEWER REMOVAL 36"	FOOT	15
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	36
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	568
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1
60262700	INLETS TO BE RECONSTRUCTED	EACH	2
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1137.5
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1
63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	1
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5
67100100	MOBILIZATION	L SUM	1
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1
78200410	GUARDRAIL MARKERS, TYPE A	EACH	14
Z0029652	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	13765

PAY CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY I-74 RURAL 90% FEDERAL 10% STATE 0021
Z0029654	HIGH TENSION CABLE MEDIAN BARRIER TERMINALS	EACH	16
Z0076870	UNDERDRAIN CONNECTION TO STRUCTURE	EACH	19
XZ193300	SURVEY MARKER, TYPE 1 (SPECIAL)	EACH	4
X0322463	CONNECTION TO EXISTING SEWER	EACH	9
X0323583	SPEED INDICATOR SIGN	CAL DA	150
X0325588	HIGH TENSION CABLE MEDIAN BARRIER DEMONSTRATION	L SUM	1
X0325667	WEED CONTROL MOWING STRIP (SPECIAL)	SQ YD	6473
X0484300	MEDIAN INLET BOX REMOVAL	EACH	18
X6330104	REMOVE AND RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL, FLARED	EACH	1
X6340205	GUARD POSTS REMOVAL	EACH	13
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = davsorkb	DESIGNED -	REVISED -
cs:\pw\work\p\dot\davsorkb\d0247724\050910-shr-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	HSIP FY2011-4	VERMILION	88	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70910	