

3:51:37 PM

Mar-25-2011 03:51:37PM

\$FILE\$

CONTRACT NO. 72667

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	69-3(3HB)	MORGAN	793	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

80% FEDERAL 20% STATE
CONSTRUCTION AND SAFETY TYPE CODE

CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE	
					0001 ROADWAY	0008 STRUCTURE
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)		UNIT	299	299	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)		UNIT	534	534	
20100500	TREE REMOVAL, ACRES		ACRE	18.9	18.9	
20200100	EARTH EXCAVATION	.	CU YD	647,963	647,963	⚠
20200200	ROCK EXCAVATION		CU YD	100	100	
20200500	EARTH EXCAVATION (WIDENING)	.	CU YD	130	130	
20400800	FURNISHED EXCAVATION		CU YD	436,880	436,880	⚠
20700220	POROUS GRANULAR EMBANKMENT		CU YD	40	40	
20800150	TRENCH BACKFILL		CU YD	4665	4665	
21101615	TOPSOIL FURNISH AND PLACE, 4"		SO YD	877140	877140	
21400100	GRADING AND SHAPING DITCHES	.	FOOT	500	500	
* 25000200	SEEDING, CLASS 2		ACRE	230	230	
* 25000350	SEEDING, CLASS 7		ACRE	40	40	
* 25000400	NITROGEN FERTILIZER NUTRIENT		POUND	20700	20700	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	20700	20700	
* 25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	20700	20700	
* 25000700	AGRICULTURAL GROUND LIMESTONE		TON	460	460	
* 25003200	INTERSEEDING, CLASS 2		ACRE	10	10	
* 25100115	MULCH, METHOD 2		ACRE	270	270	
* 25100635	HEAVY DUTY EROSION CONTROL BLANKET		SO YD	7197	7197	
28000200	EARTH EXCAVATION FOR EROSION CONTROL		CU YD	1000	1000	
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	75000	75000	
28000400	PERIMETER EROSION BARRIER		FOOT	7000	7000	
28000500	INLET AND PIPE PROTECTION		EACH	80	80	
28001000	AGGREGATE (EROSION CONTROL)		TON	1500	1500	
28100707	STONE DUMPED RIPRAP, CLASS A4	.	SQ YD	19885	19885	
28100709	STONE DUMPED RIPRAP, CLASS A5	.	SQ YD	426	426	

*SPECIALTY ITEM

⚠ REVISIED 6-6-11

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
FAP 310 (US 67/IL 104)
SHEET 1 OF 13

DATE 10/2010
DRAWN BY B G J
CHECKED BY E B B