

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ACBRT		
				ACTM 0004 LIC 90%FED. 10%STATE	0011 LIC 90%FED. 10%STATE	0040 LIC 90%FED. 10%STATE
28100105	STONE RIPRAP, CLASS A3	SQ YD	2352	2352		
28100107	STONE RIPRAP, CLASS A4	SQ YD	1645	43	1602	
28200200	FILTER FABRIC	SQ YD	4358	2756	1602	
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	12272	12272		
30201500	LIME	TON	246.1	246.1		
31100200	SUBBASE GRANULAR MATERIAL, TYPE A	CU YD	277	277		
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	68296	68296		
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	796	796		
31200100	STABILIZED SUBBASE 4"	SQ YD	57810	57810		
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	17088	17088		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1000	1000		
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4291	4291		
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	9629	9629		
40300500	COVER COAT AGGREGATE	TON	104	104		
40300600	SEAL COAT AGGREGATE	TON	104	104		
<del>40600100</del>	<del>BITUMINOUS MATERIALS (PRIME COAT)</del>	<del>GALLON</del>	<del>8788</del>	<del>8788</del>		
<del>40600300</del>	<del>AGGREGATE (PRIME COAT)</del>	<del>TON</del>	<del>28</del>	<del>28</del>		
40603000	HOT-MIX ASPHALT BINDER COURSE, IL-12.5, N50	TON	1760	1760		
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	633	633		
40701941	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13"	SQ YD	7154	7154		
40701961	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14"	SQ YD	23390	23390		
42000541	PORTLAND CEMENT CONCRETE PAVEMENT 12" (JOINTED)	SQ YD	3416	3416		
42001300	PROTECTIVE COAT	SQ YD	12837	12837		
42100340	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 12"	SQ YD	33402	33402		
42100615	PAVEMENT REINFORCEMENT	SQ YD	33402	33402		
42101020	WIDE FLANGE BEAM TERMINAL JOINT COMPLETE 24'	EACH	4	4		
42101030	WIDE FLANGE BEAM TERMINAL JOINT COMPLETE 36'	EACH	4	4		
42101300	PROTECTIVE COAT	SQ YD	66796	66796		
44000100	PAVEMENT REMOVAL	SQ YD	51950	51950		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	10989	10989		
44004000	PAVED DITCH REMOVAL	FOOT	1395	1395		

▲ REVISED 6-7-11

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -			270	60-1B-1	MADISON	712	7
		CHECKED -	REVISED -			CONTRACT NO. 76A91				
		DATE -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				