

PROPOSED SIGN STRUCTURE SCHEDULE																
ALIGNMENT	LOCATION			SIGN PANEL TYPE 3 (SQ FT)	NO. OF POSTS	BREAKAWAY WIDE FLANGE STEEL POSTS				STRUCT STEEL SIGN SUPPORT BREAKAWAY	CONCRETE FOUNDATIONS	REINFORCEMENT BARS	OVERHEAD SIGN STRUCTURE SPAN TYPE I-A	DRILLED SHAFT CONCRETE FOUNDATION	OVERHEAD SIGN STRUCTURE WKWY TYPE A	NOTES
	PROP. STA I-270	OFFSET CL TO CENTER OF SIGN FT	LEGEND			POST TYPE AND SIZE	FIRST POST LENGTH	SECOND POST LENGTH	THIRD POST LENGTH							
I-270	1159+00	75 RT	ILLINOIS 3 / EFFINGHAM / INDIANAPOLIS MILEAGE	129.50	2	W10 X 26	18	21		1,170	2.54	196				
I-270	1164+00	75 RT	CLICK IT OR TICKET	80.00	2	W 10 X 22	18' - 10"	20' - 10"		1,005	2.36	184				
I-270	1169+75	90 RT	IL 3 ALTON GRANITE CITY 1 MILE	239.25	3	W16 X 45	30'-7"	32'-6"	34'-6"	4,864	6.69	390				
I-270	1179+00	65 RT	NOTICE MOVE OVER - SLOW DOWN	132.00	2	W10 X 26	17' - 11"	21' - 3"		1,174	2.54	196				
I-270	1189+00	85 RT	IL 3 SOUTH / GRANITE CITY NEXT RIGHT	189.75	3	W16 X 45	29' - 4"	31' - 4"	33' - 4"	4,702	6.69	390				
I-270	1212+00	65 RT	GREAT RIVER ROAD	168.75	2	W14 X 38	26' - 3"	25' - 0"		2,214	4.18	244				
			EXIT 4	41.25												
			IL 203 / GRANITE CITY / 1 1/2 MILES	173.25												
			EXIT 3B	31.25												
			IL 3 NORTH / ALTON / NEXT RIGHT	112.50									80	44.3	58	OVERHEAD SIGN STRUCTURE MOUNTED ON NEW TRUSS
			EXIT 3A	50.00												
			IL 3 SPUR SOUTH / GRANITE CITY	170.00												
I-270	1226+00	140 RT	LODGING	42.50	2	W 6 X 9	11' - 8"	11' - 11"		253	1.4	156				
			TOTALS	1560.00	16					15,382	26.4	1,756	80	44.3	58	

GUARDRAIL MARKERS		
ALIGNMENT (LOCATION)	GUARDRAIL MARKERS - TYPE A (EA)	
	ONE WAY WHITE	ONE WAY AMBER
EX-270 (RT)		
120+65 TO 154+70	23	
132+19 TO 155+32		16
EX-270 (LT)		
120+66 TO 154+70	20	
132+19 TO 155+52		17
PR-270 (RT)		
1156+56 TO 1160+56		5
1160+56 TO 1177+21		5
1155+00 TO 1191+76	10	
1224+99 TO 1231+56		6
1230+27 TO 1231+60	1	
PR-270 (LT)		
1156+87 TO 1177+00		10
1155+00 TO 1191+76	14	
1224+82 TO 1231+60		7
RAMP P-4 (RT)		
11214+53 TO 11217+54	2	
RAMP P-1 (RT)		
21160+92 TO 21162+93	3	
21180+44 TO 21184+03	5	
TOTAL		144