REMOVAL SCHEDULE

SHEET	STATION	TO	STATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER) UNIT	TREE REMOVAL (OVER 15 UNITS DIAMETER) UNIT	TREE REMOVAL, ACRES ACRE	PAVEMENT REMOVAL SQ YD	DRIVEWAY PAVEMENT REMOVAL SQ YD	SIDEWALK REMOVAL SQ FT	CURB REMOVAL FOOT	CONCRETE REMOVAL CU YD	REMOVE SING PANEL ASSEMBLY - TYPE B EACH
PLAN-1	190+92.60	TO	195+75.00	-	-	-	-	-	-	36	-	-
PLAN-2	195+75.00	TO	84+97.91	76	121	0.06	1,085	41	967	-	-	-
PLAN-3	7+00.00	TO	END	-	-	0.19	441	-	762	36	60	2
			TOTALS	**76**	**121**	**0.25**	**1,526**	**41**	**1,729**	**72**	**60**	**2**

NOTES

1. ASSUME 12" THICKNESS FOR CONCRETE REMOVAL.

FENCE SCHEDULE

SHEET	STATION	TO	STATION	TEMPORARY CHAIN LINK FENCE FOOT
PLAN-1	190+92.60	TO	195+75.00	-
PLAN-2	195+75.00	TO	84+97.91	-
PLAN-3	7+00.00	TO	END	543
			TOTALS	**543**

PATCHING SCHEDULE

SHEET	STATION	TO	STATION	CLASS C PATCHES, TYPE IV, 9 INCH SQ YD
PLAN-1	190+92.60	TO	195+75.00	-
PLAN-2	195+75.00	TO	84+97.91	-
PLAN-3	7+00.00	TO	END	46
			TOTALS	**46**

PAVEMENT SCHEDULE

SHEET	STATION	TO	STATION	SUB-BASE GRANULAR MATERIAL, TYPE B 4" SQ YD	CONCRETE CURB, TYPE B FOOT
PLAN-1	190+92.60	TO	195+75.00	292	36.0
PLAN-2	195+75.00	TO	84+97.91	-	-
PLAN-3	7+00.00	TO	END	-	36.0
			TOTALS	**292**	**72.0**