

REMOVAL SCHEDULE

SHEET	STATION	TO	STATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL, ACRES	PAVEMENT REMOVAL	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	PAVED SHOULDER REMOVAL	CONCRETE REMOVAL	GUARDRAIL REMOVAL	POLE BUILDING REMOVAL	FENCE REMOVAL	PAVED DITCH REMOVAL
				UNIT	ACRE	SQ YD	FOOT	SQ YD	CU YD	FOOT	EACH	FOOT	SQ YD
PLAN-1	59+00.00	TO	65+00.00	-	-	243	464.0	568	-	165	-	61	-
PLAN-2	65+00.00	TO	71+00.00	31	0.19	2	259.0	259	-	264	1	559	-
PLAN-3	71+00.00	TO	77+00.00	97	0.75	-	-	-	-	-	-	-	-
PLAN-4	77+00.00	TO	83+00.00	37	0.02	-	-	-	215	-	-	-	-
PLAN-5	83+00.00	TO	196+00.00	-	-	-	-	-	64	-	-	-	-
PLAN-6	196+00.00	TO	191+00.00	-	-	-	-	-	-	-	-	-	-
PLAN-7	60+00.00	TO	66+00.00	-	-	-	-	-	-	33	-	-	-
PLAN-8	66+00.00	TO	72+00.00	-	-	-	61.0	139	-	-	-	-	104
PLAN-9	DETENTION BASIN PLAN			-	1.06	-	-	-	335	-	-	404	-
PLAN-9	CSX ACCESS ROAD			-	0.22	-	-	-	-	-	-	-	-
TOTALS				165	2.25	245	784.0	966	614	512	1	1,024	104

NOTE:
1. TREE REMOVAL, ACRES TOTAL IS ROUNDED UP TO THE NEAREST 0.25 ACRE.

FENCE SCHEDULE

SHEET	STATION	TO	STATION	CHAIN LINK FENCE, 6'	CHAIN LINK GATES, 6' x 16' DOUBLE	CHAIN LINK FENCE, 10' (SPECIAL)
				FOOT	EACH	FOOT
PLAN-1	59+00.00	TO	65+00.00	-	-	260
PLAN-2	65+00.00	TO	71+00.00	-	-	413
PLAN-3	71+00.00	TO	77+00.00	63	-	-
PLAN-4	77+00.00	TO	83+00.00	-	-	-
PLAN-5	83+00.00	TO	196+00.00	-	-	-
PLAN-6	196+00.00	TO	191+00.00	-	-	-
PLAN-7	60+00.00	TO	66+00.00	-	-	-
PLAN-8	66+00.00	TO	72+00.00	-	-	-
PLAN-9	DETENTION BASIN PLAN			510	2	100
PLAN-9	CSX ACCESS ROAD			-	-	-
TOTALS				573	2	773

PAVEMENT SCHEDULE

SHEET	STATION	TO	STATION	POROUS GRANULAR EMBANKMENT	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	AGGREGATE BASE COURSE, TYPE A 12"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	PROTECTIVE COAT	PORTLAND CEMENT CONCRETE SHOULDERS 10"	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/2"	CONCRETE GUTTER, TYPE A	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (MODIFIED)	CONCRETE MEDIAN SURFACE, 4 INCH	PAVED DITCH (SPECIAL)
				CU YD	SQ YD	SQ YD	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	FOOT	FOOT	SQ FT	FOOT	
PLAN-1	59+00.00	TO	65+00.00	15	1,283	2,356	0.3	1.1	117	1,208	-	2,018	520	499	-	-	466.0	104.0	-
PLAN-2	65+00.00	TO	71+00.00	-	1,615	2,155	0.2	0.6	59	1,615	-	1,986	260	267	-	-	259.0	-	-
PLAN-3	71+00.00	TO	77+00.00	-	758	884	-	-	-	487	316	952	-	81	202.5	-	-	-	-
PLAN-4	77+00.00	TO	83+00.00	1,474	-	-	-	-	-	-	-	-	-	-	-	-	-	16,383	-
PLAN-5	83+00.00	TO	196+00.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
PLAN-6	196+00.00	TO	191+00.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
PLAN-7	60+00.00	TO	66+00.00	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
PLAN-8	66+00.00	TO	72+00.00	-	-	139	0.1	0.3	32	-	-	114	139	-	-	61.0	-	-	122
PLAN-9	DETENTION BASIN PLAN			-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-
PLAN-9	CSX ACCESS ROAD			-	-	1,267	-	-	-	-	-	-	-	-	-	-	-	-	-
TOTALS				1,489	3,656	6,801	0.6	2.0	208	3,310	316	5,070	919	847	202.5	61.0	725.0	16,487	122

USER NAME = Henaoc	DESIGNED - OP	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 2,000' / in.	DRAWN - OP	REVISED -					70	82-1-B-1	ST. CLAIR	319	18
PLOT DATE = \$DATE\$	CHECKED - DBM	REVISED -		SCALE: NONE SHEET NO. 1 OF 3 SHEETS STA. TO STA.			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				
	DATE - 3-30-11	REVISED -		CONTRACT NO. 76C75							