

GUARDRAIL SCHEDULE												
LOCATION			SIDE	GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 2	GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKER - DIRECT APPLIED
STATION	TO	STATION	RT/LT	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH	EACH
405+23.04	TO	407+58.21	RT	99	150	1	1		3			1
407+58.21	TO	409+56.86	RT/LT							6	6	
409+56.86	TO	411+52.64	LT	104	112.5	1	1		2			1
415+39.96	TO	416+62.08	RT		37.5	1	1		2			1
415+64.90	TO	416+99.12	LT		50	1	1		2			1
416+62.08	TO	419+97.92	RT/LT							6	6	
418+60.88	TO	420+20.26	RT	207	87.5	1	1		2			1
418+97.92	TO	836+51.08	LT	442	375		2		6			
836+51.08	TO	425+79.04	LT	331	262.5		2		6			
425+25.27	TO	425+60.70	RT	54			1		2			
425+60.70	TO	427+31.71	RT/LT							4	4	
427+13.74	TO	427+89.15	RT	60	37.5		1	1	2			
427+31.71	TO	428+16.09	LT	88		1	1		1			1
429+35.59	TO	434+10.59	RT	476	375		2		6			2
431+18.00	TO	439+10.30	LT	912	800		2		11			2
TOTALS				2773	2287.5	10	12	1	45	16	16	10