

SUMMARY OF QUANTITIES					SUMMARY OF QUANTITIES										
URBAN					URBAN										
CODE NO.	ITEM	CONSTRUCTION TYPE CODE		0003		0021		CODE NO.	ITEM	CONSTRUCTION TYPE CODE		0003		0021	
		UNIT	TOTAL QUANTITIES	ROADWAY 80% FEDERAL 20% STATE	TRAFFIC SIGNALS 80% FEDERAL 20% STATE	UNIT	TOTAL QUANTITIES			ROADWAY 80% FEDERAL 20% STATE	TRAFFIC SIGNALS 80% FEDERAL 20% STATE	UNIT	TOTAL QUANTITIES	ROADWAY 80% FEDERAL 20% STATE	TRAFFIC SIGNALS 80% FEDERAL 20% STATE
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	5.9	5.9		81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	90		90				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	166	166		81012900	CONDUIT IN TRENCH, 3 1/2" DIA., PVC	FOOT	34		34				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4023	4023		81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	143		143				
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	111	111		81021330	CONDUIT, PUSHED, 2" DIA., PVC	FOOT	126		126				
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	226	226		81021340	CONDUIT, PUSHED, 2 1/2" DIA., PVC	FOOT	26		26				
60618300	CONCRETE MEDIAN SURFACE, 4"	SQ FT	17235	17235		81021350	CONDUIT, PUSHED, 3" DIA., PVC	FOOT	162		162				
60622400	CONCRETE MEDIAN, TYPE SM-6.06	SQ FT	3061	3061		81021370	CONDUIT, PUSHED, 4" DIA., PVC	FOOT	115		115				
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FT POSTS	FOOT	287.5	287.5		81400100	HANDHOLE	EACH	10		10				
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2		81500100	GULFBOX JUNCTION	EACH	3		3				
*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		*81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP - TYPE USE) 3-1/C NO. 10	FOOT	1029		1029				
66400105	CHAIN LINK FENCE, 4'	FOOT	625	625		*81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1159		1159				
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3	3		*82103900	LUMINAIRE, SODIUM VAPOR, MULTIMOUNT, 250 WATT	EACH	8		8				
67100100	MOBILIZATION	L SUM	1	1		*82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT 60AMP	EACH	1		1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	11	11		*83600350	LIGHT POLE FOUNDATION METAL, 11" BOLT CIRCLE, 8" X 6'	EACH	1		1				
X7010210	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		*85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	50	50		*86200300	UNINTERRUPTIBLE POWER SUPPLY, EXTENDED	EACH	1		1				
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	24	24		*87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5/C	FOOT	1229		1229				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3591	3591		*87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7/C	FOOT	1743		1743				
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	404	404		*87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9/C	FOOT	1080		1080				
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	6405	6405		*87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 12/C	FOOT	516		516				
70300260	TEMPORARY PAVEMENT MARKING-LINE 12"	FOOT	463	463		*87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4901		4901				
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	226	226		87700160	STEEL MAST ARM ASSEMBLY AND POLE 24 FT.	EACH	1		1				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4966	4966		87700180	STEEL MAST ARM ASSEMBLY AND POLE 28 FT.	EACH	1		1				
72400730	RELOCATE SIGN PANEL - TYPE 3	SQ FT	210	210		87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	4		4				
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1567	1567		87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6		6				
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	4	4		87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3		3				
*78004200	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	544	544		87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	20		20				
*78004210	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	9805	9805		87800415	CONCRETE FOUNDATION, TYPE E, 36-INCH DIAMETER	FOOT	60		60				
*78004250	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	463	463		*88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2		2				
*78004280	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	309	309		*88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	14		14				
*78200410	GUARDRAIL MARKERS, TYPE A	EACH	7	7		*88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	4		4				
*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		*88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	2		2				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1383	1383		*88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED	EACH	2		2				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	52	52		*88200100	TRAFFIC SIGNAL BACKPLATE	EACH	16		16				
80300100	LOCATING UNDERGROUND CABLE	FOOT	30		30	*88500100	INDUCTIVE LOOP DETECTOR	EACH	13		13				
80500105	SERVICE INSTALLATION, TYPE A (MODIFIED)	EACH	1	1	1	*88500200	INDUCTIVE LOOP DETECTOR WITH SYSTEM OUTPUT	EACH	5		5				
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	688		688	*88600100	DETECTOR LOOP, TYPE 1	FOOT	2328		2328				
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	108		108	*89501250	RELOCATE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1				
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	105		105	*89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		1				

*SPECIALTY ITEM

FILE NAME =	USER NAME = knightam	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
en\pw\work\pw\dot\knightam\d0167472\7815	5-sht-schedule.dgn	DRAWN -	REVISED -		331	(1X-1)R-1,RS-2,N-2,TS-3	WILLIAMSON	167	7				
PLOT SCALE = 50.00'96" / IN.	CHECKED -	REVISED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				ILLINOIS FED. AID PROJECT				
PLOT DATE = 3/23/2011	DATE -	REVISED -	REVISED -						CONTRACT NO. 78155				