

PAVEMENT REPAIR AND PATCHING SCHEDULE

STATION (CENTER OF PATCH)	SIZE (FOOT)	PAVEMENT REMOVAL (SPECIAL) (SQ YD)	PAVEMENT REMOVAL (SQ YD)	SUBBASE GRANULAR MATERIAL TYPE A, 4" (SQ YD)	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED) (SQ YD)	PROTECTIVE COAT (SQ YD)	PORTLAND CEMENT CONCRETE INLAY, 3" (SQ YD)	CLASS B PATCHES TYPE IV 10 INCH (SQ YD)	SAW CUTS (FOOT)	DOWEL BARS 1 1/2" (EACH)	PAVEMENT FABRIC (SQ YD)
US 45											
27+70 TO 29+70 LT.	200 X 12		267	267	267	267					267
29+46 RT.	12 X 9	12					12		186		
29+75 RT.	6 X 6	4					4		72		
29+80 C. L.	12 X 6	8					8		132		
30+49 RT.	6 X 9	6					6		102		
31+42 LT.	6 X 6	4					4		72		
IL 13											
1075+44 LT.	12 X 6	8					8		132		
1075+92 RT.	6 X 9	6					6		102		
1076+06 C. L.	12 X 6	8					8		*120		
1076+08 LT.	15 X 15							25	90	28	25
1076+50 RT.	12 X 12	16					16		240		
1076+68 RT.	6 X 15	10					10		*144		
1076+71 RT.	3 X 9	3					3		*54		
1076+74 C. L.	3 X 9	3					3		60		
1076+92 LT.	6 X 9	6					6		102		
1076+96 LT.	6 X 3	2					2		42		
1077+05 RT.	6 X 3	2					2		42		
1077+65 LT.	12 X 6	8					8		132		
TOTALS		106	267	267	267	267	106	25	1824	28	292

*SAWCUT QUANTITY HAS BEEN REDUCED DUE TO PROPOSED SAWCUT FROM ADJOINING PATCH

FILE NAME =	USER NAME = neesdp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES (PAVEMENT REPAIR AND PATCHING)	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct\pwork\pwork\neesdp\d0253881\78240	ght-plan.dgn	DRAWN -	REVISED -			331/332D9	CM PAVEMENT REPAIR 2011-1	SALINE	6	5	
	PLOT SCALE = 80.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 78240					
	PLOT DATE = 3/28/2011	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO. OF SHEETS		STA. TO STA.			