

ENTRANCES							40800050
Ent #	Location		Type	WIDTH		AREA	INCIDENTAL HMA
	Station	Side	Private/Field	At Row	At Roadway	(SQ YD)	(TON)
1	Sta 12+00	Lt.	Field	35	56	15.17	N/A
2	Sta 21+50	Rt.	Field	35	60	15.83	N/A
3	Sta 27+28.50	Rt.	Private	18	36	68.12	19.86
4	Sta 35+00	Rt.	Field	35	60	15.83	N/A
5	Sta 38+50	Rt.	Field	35	49	14.00	N/A
6	Sta 38+75	Lt.	Field	35	52	14.50	N/A
7	Sta 42+92.50	Lt.	Private	17	38	74.70	22.02
8	Sta 62+00	Lt.	Private	20	38	83.90	24.94
9	Sta 75+00	Rt.	Field	35	53	14.67	N/A
10	Sta 89+76.70	Rt.	Field	48	60	18.00	N/A
11	Sta 89+85.40	Lt.	Field	48	60	18.00	N/A
12	Sta 102+00	Lt.	Field	35	56	15.17	N/A
13	Sta 103+79.50	Lt.	Private	20	45	115.03	35.01
14	Sta 115+00	Rt.	Field	28	41	11.50	N/A
15	Sta 117+57	Rt.	Field	35	60	15.83	N/A
16	Sta 120+10	Lt.	Field	35	49	14.00	N/A
17	Sta 123+75	Lt.	Field	35	54	14.83	N/A
18	Sta 143+50	Lt.	Field	48	60	18.00	N/A
19	Sta 143+52	Rt.	Field	48	60	18.00	N/A
20	Sta 169+33.82	Rt.	Field	35	60	15.83	N/A
21	Sta 174+05.50	Lt.	Private	20	40	87.40	26.01
22	Sta 184+49.50	Lt.	Private	24	40	96.93	28.98
23	Sta 197+24.54	Rt.	Field	48	60	18.00	N/A
24	Sta 197+24.54	Lt.	Field	48	60	18.00	N/A
25	Sta 211+26	Lt.	Field	35	50	14.17	N/A
26	Sta 211+54.40	Rt.	Private	20	38	88.96	26.64
27	Sta 212+76.68	Rt.	Private	20	45	88.96	26.25
28	Sta 248+00	Rt.	Field	35	50	14.17	N/A
29	Sta 250+75	Lt.	Field	35	50	14.17	N/A
30	Sta 251+25.80	Rt.	Private	35	60	113.13	32.69
31	Sta 258+76.69	Lt.	Field	35	50	14.17	N/A
32	Sta 258+76.69	Rt.	Field	35	50	14.17	N/A
33	Sta 267+00	Lt.	Field	35	50	14.17	N/A
34	Sta 267+00	Rt.	Field	35	50	14.17	N/A
35	Sta 1500+83.23	Lt.	Field	35	47	13.67	N/A
36	Sta 1503+17.59	Lt.	Field	35	47	13.67	N/A
37	Sta 1503+17.59	Rt.	Field	35	47	13.67	N/A
38	Sta 1603+16.15	Lt.	Field	35	40	12.50	N/A
39	Sta 1603+16.15	Rt.	Field	35	50	14.67	N/A
40	Sta 1901+00	Lt.	Field	30	50	13.33	N/A
41	Sta 1901+00	Rt.	Field	30	50	13.33	N/A
42	Sta 1903+50	Lt.	Field	30	50	13.33	N/A
43	Sta 1903+50	Rt.	Field	30	50	13.33	N/A
TOTAL=						1322.98	242.40
USE=							250 TONS

Note: 3 FT APRON TO BE CONSTRUCTED ON ALL ENTRANCES DURING MAINLINE PAVING OPERATION AND QUANTITIES ARE INCLUDED WITHIN MAINLINE CONSTRUCTION.

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
FAS 358	86-00075-04-PV	WOODFORD	33	7
CONTRACT NO.			89596	

SCHEDULE OF ENTRANCES	
CALC. BY: KK	DATE: 04/12/11
CHECK BY: BH	DATE: 04/12/11