

CODE NO.	PAY ITEM	UNIT	TOTAL	CONSTRUCTION CODES	
				0004 ROADWAY	0011 STRUCTURE 057-7841
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	8	8	
* 20200100	EARTH EXCAVATION	CU YD	266	266	
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	408		408
20700220	POROUS GRANULAR EMBANKMENT	CU YD	500		500
20800150	TRENCH BACKFILL	CU YD	160	160	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	200	200	
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	182	182	
25000110	SEEDING, CLASS 1A	ACRE	0.4	0.4	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	36	36	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	36	36	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	36	36	
25100115	MULCH, METHOD 2	ACRE	0.4	0.4	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	880	880	
28000400	PERIMETER EROSION BARRIER	FOOT	150	150	
28000500	INLET AND PIPE PROTECTION	EACH	13	13	
* 31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	1,100	1,100	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	100	100	
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10	10	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	20	20	
42001300	PROTECTIVE COAT	SQ YD	1,810	1,810	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	200	200	
* 42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1,375	1,375	
* 42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	230	230	
* 44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	80	80	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,150	1,150	
44000600	SIDEWALK REMOVAL	SQ FT	1,700	1,700	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
50104650	SLOPE WALL REMOVAL	SQ YD	324		324
50300225	CONCRETE STRUCTURES	CU YD	29.0		29.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	131.8		131.8
50300260	BRIDGE DECK GROOVING	SQ YD	417		417
50300300	PROTECTIVE COAT	SQ YD	610		610
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	138,560		138,560
* 51100300	SLOPE WALL 6 INCH	SQ YD	691		691
51500100	NAME PLATES	EACH	1		1
54003000	CONCRETE BOX CULVERTS	CU YD	555.1		555.1
* 550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	210	210	
* 550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	30	30	

* SPECIAL PROVISION

CODE NO.	PAY ITEM	UNIT	TOTAL	CONSTRUCTION CODES	
				0004 ROADWAY	0011 STRUCTURE 057-7841
55100300	STORM SEWER REMOVAL 8"	FOOT	35	35	
55100400	STORM SEWER REMOVAL 10"	FOOT	220	220	
55100500	STORM SEWER REMOVAL 12"	FOOT	120	120	
* 56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	6	6	
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	10	10	
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60221700	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1	
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	3	3	
60255500	MANHOLES TO BE ADJUSTED	EACH	3	3	
* 60266600	VALVE BOXES TO BE ADJUSTED	EACH	3	3	
60500060	REMOVING INLETS	EACH	6	6	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	830	830	
61139900	STORM SEWERS, (SPECIAL), 6"	FOOT	50	50	
61140000	STORM SEWERS, (SPECIAL), 8"	FOOT	50	50	
61140100	STORM SEWERS, (SPECIAL), 10"	FOOT	50	50	
61140200	STORM SEWERS, (SPECIAL), 12"	FOOT	50	50	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
* Z0026407	TEMPORARY SHEET PILING	SQ FT	2,485		2,485
* Z0034100	MASONRY WALL CONSTRUCTION	SQ FT	165		165
* LR420029	PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL)	SQ YD	1,200	1,200	
Δ X0323200	SANITARY SEWER, DUCTILE IRON, 12"	FOOT	65	65	
* X0323221	PLUG AND ABANDON EXISTING PIPE	CU YD	3.5	3.5	
* X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	408		408
* X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	80	80	
* X4404400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	1,475	1,475	
Δ X5091765	PIPE HANDRAIL, SPECIAL	FOOT	102		102
* X5504200	DUCTILE IRON STORM SEWER, 12 INCH	FOOT	110	110	
* X6020076	INLETS, SPECIAL, WITH SPECIAL FRAME AND GRATE	EACH	4	4	
* X6022230	MANHOLES, TYPE A, 4' DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	2	2	
* X6022810	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2	
* XX008532	STORM SEWER, DUCTILE IRON, 14 INCH	FOOT	95	95	
* XX008533	STORM SEWER, DUCTILE IRON, 16 INCH	FOOT	90	90	

* SPECIAL PROVISION

Δ SPECIALTY ITEMS

FILED & DATED
 BY/Town of Normal/2008/08/08/081 Broadway Ave Br/g/dg

DESIGNED - BAB/JCZ	REVISED -
DRAWN - JTC/JWK	REVISED -
CHECKED - MSW	REVISED -
DATE - 02/25/11	REVISED -

TOWN OF NORMAL

SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET NO. 3 OF 40 SHEETS STA. 8+30 TO STA. 11+75

**BROADWAY AVENUE OVER SUGAR CREEK
SECTION 07-00233-00-BR
MCLEAN, COUNTY**

F.A.U.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	07-00233-00-BR	MCLEAN	40	3
S.N. 057-7841			CONTRACT NO. 91422	
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				