



TEMPORARY SHEET PILING DATA

Top Elevation = 767.27
 Tip Elevation = 737.77 (at end)
 Tip Elevation = 755.77 (at center)
 Min. Section Modulus = 26.3 in³/ft
 Area = 2.485 ft²

NOTES:

- 1.) Contractor to locate utilities, especially the 24" Watermain, before driving sheet piling.
- 2.) The unit price bid for Temporary Sheet Piling shall also include any "Block Outs" or cutting necessary for utilities.

**TEMPORARY SHEET PILING DETAIL
 STRUCTURE NO. 057-7841**

DESIGNED JCZ
CHECKED MSW
DRAWN JWK
CHECKED MSW

DATE 02/25/11

SHEET NO. C4	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		07-00233-00-BR	MCLEAN	40	19
19 SHEETS	SN 057-7841		CONTRACT NO. 91422		
FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT					