INCIDENTAL HOT-MIX ASPHALT SURFACING

LOCATION	INCIDENTAL HOT-MIX ASPHALT SURFACING (40800050)
	TON
STA 48+76.24, RT	0.5
STA 301+34.92, RT	0.7
STA 301+48.82, LT	0.5
STA 303+04.52, RT	0.7
STA 304+23.92, LT	0.8
STA 305+67.82, RT	0.6
STA 306+33.68, RT	0.5
STA 306+88.38, RT	0.6
STA 306+96.59, LT	0.7
STA 307+08.01, RT	0.6
STA 307+66.88, RT	0.5
STA 307+82.96, RT	0.6
STA 308+41.43, LT	0.6
STA 308+84.72, RT	0.6
STA 309+54.70, RT	1.0
STA 310+77.94, RT	0.6
STA 310+90.70, LT	1.1
STA 311+02.41, RT	0.6
STA 311+54.03, RT	0.7
STA 313+34.30, LT	0.8
STA 313+65.35, RT	0.6
STA 315+96.09, LT	0.8
STA 316+28.02, RT	0.6
STA 316+46.19, LT	0.6
STA 316+49.77, RT	0.9
STA 317+61.32, RT	0.9
STA 320+14.21, RT	3.0
STA 299+22.30, LT	1.4
CHAUCER BOULEVARD	28.4
WEST TATMAN ENTRANCE	6.0
EAST TATMAN ENTRANCE	5.1
WEST MIDDLE SCHOOL ENTRANCE	13.4
TOTAL	75.0

DOMESTIC METER VAULTS TO BE ADJUSTED SCHEDULE

LOCATION	DOMESTIC METER VAULTS TO BE ADJUSTED (56500300)
	EACH
STA 195+84.85, 23.45' RT	1
STA 201+12.17, 22.94' RT	1
STA 202+48.53, 43.24' LT	1
STA 202+94.78, 35.43' RT	1
STA 314+77.06, 23.90' RT	1
TOTAL	5

SEGMENTAL CONCRETE BLOCK WALL SCHEDULE

LOCATION	SEGMENTAL CONCRETE BLOCK WALL (Z0013302)
	SQ FT
NE CORNER WASHINGTON/BUCHANAN	133
SE CORNER WASHINGTON/BUCHANAN	230
SW CORNER WASHINGTON/BUCHANAN	91
TOTAL	434

VALVE BOXES TO BE ADJUSTED SCHEDULE

LOCATION	VALVE BOXES TO BE ADJUSTED (60266600)
	EACH
STA 194+22.29, 23.66' LT	1
STA 194+60.26, 23.20' LT	1
STA 203+15.27, 18.79' LT	1
STA 302+82.91, 8.15' LT	1
STA 302+84.77, 15.27' LT	1
STA 309+37.65, 31.50' LT	1
STA 309+42.48, 19.42' LT	1
STA 312+50.10, 16.12' LT	1
TOTAL	8

PCC DRIVEWAY PAVEMENT SCHEDULE

LOCATION	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 6" (42300200)	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8" (42300400)
	SQ YD	SQ YD
STA 49+17.37, LT	17.1	
STA 49+22.00, RT	13.2	
STA 195+36.00, LT	21.4	
STA 195+91.38, LT	21.6	
STA 195+92.39, RT	19.4	
STA 196+62.12, RT	26.1	
STA 196+74.58, LT	33.5	
STA 197+18.57, RT		18.0
STA 197+65.03, RT		36.0
STA 198+69.29, LT		33.0
STA 201+17.6/+34.76, RT	34.0	
STA 201+43.24, LT	35.7	
TOTALS	222	87

PCC BASE COURSE WIDENING SCHEDULE

LOCATION	PCC BASE COURSE WIDENING 7" (35400200)	PCC BASE COURSE WIDENING 9" (35400400)
	SQ YD	SQ YD
NW CORNER CENTER/BUCHANAN	29	
SW CORNER CENTER/BUCHANAN		23
NE CORNER WASHINGTON/BUCHANAN		75
SW CORNER WASHINGTON/BUCHANAN		15
SE CORNER WASHINGTON/BUCHANAN		46
SW CORNER WASHINGTON/GREELY		14
SE CORNER WASHINGTON/GREELY		14
TOTALS	29	187