

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
C.H. 49	08-00162-01-RS	VERMILION	39	5

Contract No. 91459

SCHEDULE OF QUANTITIES

CLASS SI CONCRETE (OUTLET) 60600095

Station	to	Station	Cu.Yd.
Lt. 717+23.5		Lt. 717+64	2.9
Lt. 717+64		Lt. 718+00	3.5
Lt. 719+88		Lt. 720+00	0.9
Total			7.3

CONCRETE GUTTER, TYPE A (MODIFIED) 60602600

Station	to	Station	Foot
Lt. 718+00		Lt. 719+88	188.0
Total			188.0

SHORT TERM PAVEMENT MARKING 70300100

Station	to	Station	Feet
492+36(Level Binder)		805+55.5	2844.0
492+01(binder)		805+45.6	2850.0
482+66.25 (Surface)		805+55.6	2936.0
7+03 (Surface)		10+60	32.0
Total			8662.0

TEMPORARY PAVEMENT MARKING - LINE 4" 70300220

Station	to	Station	Feet	Feet	Total
			Solid White	Skip/Dash Yellow	
Lt 482+73		Lt 672+39.5	18967.0		18967.0
Lt 673+83		Lt 752+05	7822.0		7822.0
Lt 752+95		Lt 805+25.6	5231.0		5231.0
Rt 482+73		Rt 672+39.5	18967.0		18967.0
Rt 673+66.5		Rt 752+05	7839.0		7839.0
Rt 752+95		Rt 793+17.09	4022.0		4022.0
Rt 794+19		Rt 805+25.6	1107.0		1107.0
482+66.25 (C.L.)		805+55.6		8073.0	8073.0
7+03 (C.L.)		9+70		67.0	67.0
10+30 (C.L.)		10+60		8.0	8.0
Lt 7+03		Lt 9+70	267.0		267.0
Rt 7+03		Lt 805+25.6	314.0		314.0
Lt 10+30		Lt 10+60	30.0		30.0
Rt 805+25.6		Rt 10+60	77.0		77.0
					72791.0

TEMPORARY PAVEMENT MARKING - LINE 24" 70300280

Station	to	Station	Foot
Lt 482+88		(CH-49)	17.0
Rt 805+25.6		(CH-49)	11.0
Rt 9+70		(Champaign St)	9.0
Lt 10+30		(Champaign St)	9.0
Total			46.0

WORK ZONE PAVEMENT MARKING REMOVAL 70301000

Station	to	Station	Sq.Ft.
482+66.25		(C.L.) 805+55.6	979.0
7+03		(C.L.) 10+60	8.0
Total			987.0

THERMOPLASTIC PAVEMENT MARKING - LINE 4" 78000200

Station	to	Station	Foot	Foot	Total
			Solid White	Skip/Dash Yellow	
Lt 482+73		Lt 672+39.5	18967.0		18967.0
Lt 673+83		Lt 752+05	7822.0		7822.0
Lt 752+95		Lt 805+25.6	5231.0		5231.0
Rt 482+73		Rt 672+39.5	18967.0		18967.0
Rt 673+66.5		Rt 752+05	7839.0		7839.0
Rt 752+95		Rt 793+17.09	4022.0		4022.0
Rt 794+19		Rt 805+25.6	1107.0		1107.0
482+66.25		805+55.6		8073.0	8073.0
7+03		9+70		67.0	67.0
10+30		10+60		8.0	8.0
Lt 7+03		Lt 9+70	267.0		267.0
Rt 7+03		Lt 805+25.6	314.0		314.0
Lt 10+30		Lt 10+60	30.0		30.0
Rt 805+25.6		Rt 10+60	77.0		77.0
					72791.0

THERMOPLASTIC PAVEMENT MARKING - LINE 24" 78000650

Station	to	Station	Foot (White)
Lt 482+66.25		(CH-49)	17.0
Rt. 805+25.6		(CH-49)	11.0
Rt. 9+70		(Champaign St)	9.0
Lt. 10+30		(Champaign St)	9.0
Total			46.0

RAISED REFLECTIVE PAVEMENT MARKERS 78100100

Station	to	Station	Each
482+66.25		805+55.6	404.0
Total			404.0

ALLERTON-SIDELL RD. (CH 49) RESURFACING SECTION 08-00162-01-RS	Prepared by: Vermilion County Highway Dept. 2732 Batestown Road Oakwood, Illinois 61858		SCHEDULE OF QUANTITIES
	DSGN: GHS	DRN: SMW	
	CHK: GHS	DATE: 1/20/2010	