

CODE NO.	ITEM	UNIT	STU	ITEP		NON-PARTICIPATING LOCAL 0043	TOTAL QUANTITY
				0029	0031		
20200100	EARTH EXCAVATION	CU YD	471				471
20800150	TRENCH BACKFILL	CU YD	17				17
28000400	PERIMETER EROSION BARRIER	FOOT	223				223
28000500	INLET AND PIPE PROTECTION	EACH	6				6
28000510	INLET FILTERS	EACH	6				6
31100300	SUBBASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	2,095				2,095
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	193				193
35501302	HOT-MIX ASPHALT BASE COURSE, 4 1/2"	SQ YD	461				461
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	459			77	536
40600300	AGGREGATE (PRIME COAT)	TON	11				11
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	107				107
40600895	CONSTRUCTING TEST STRIP	EACH	2				2
40600990	TEMPORARY RAMP	SQ YD	139				139
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	92				92
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	600			101	701
42001300	PROTECTIVE COAT	SQ YD	92	2,969			3,061
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD		453			453
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT		15,553			15,553
42400800	DETECTABLE WARNINGS	SQ FT		244			244
44000100	PAVEMENT REMOVAL	SQ YD	987				987
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD		245			245
• 44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	416	1,518			1,934
44000600	SIDEWALK REMOVAL	SQ FT		27,062			27,062
44201325	CLASS C PATCHES, TYPE I, 8 INCH	SQ YD	6				6
44201329	CLASS C PATCHES, TYPE II, 8 INCH	SQ YD	21				21
44201333	CLASS C PATCHES, TYPE III, 8 INCH	SQ YD	22				22
44201335	CLASS C PATCHES, TYPE IV, 8 INCH	SQ YD	382				382
55100400	STORM SEWER REMOVAL 10"	FOOT	31				31
Δ • 56100600	WATER MAIN 6"	FOOT				843	843
Δ • 56100800	WATER MAIN 10"	FOOT				841	841
Δ • 56104800	WATER VALVES 4"	EACH				1	1
Δ • 56104900	WATER VALVES 6"	EACH				9	9
Δ • 56105100	WATER VALVES 10"	EACH				2	2
Δ • 56106200	ADJUSTING WATER MAIN 4"	FOOT	100				100

• SEE SPECIAL PROVISIONS  
Δ SPECIALTY ITEMS