

WATER SERVICE LINES						
STATION	SIDE	BUILDING NO. ADDRESS	WATER SERVICE LINE 1 1/2" *	WATER SERVICE LINE 1 1/2" (BORED) *	WATER SERVICE LINE 4"	WATER VALVES 4"
			FOOT			EACH
<b>SOUTH MAIN STREET</b>						
103+62.7	LT	329	15			
104+35.1	RT	320		69		
104+37.6	LT	307	15			
105+39.6	RT	314		65		
105+44.8	LT	307	15			
105+98.1	LT	301	15			
106+00.4	RT	304		65		
107+56.7	LT	229			10	1
107+62.3	RT	230		70		
107+82.9	RT	228		70		
108+13.3	LT	227	20			
108+22.2	LT	227	20			
108+35.9	RT	224		70		
108+47.0	RT	220		70		
109+16.3	RT	39 PLAZA		70		
109+84.2	RT	39 PLAZA		60		
<b>COLLEGE AVENUE</b>						
123+10.2	LT	230 SANDY		65		
<b>TOTAL</b>			100	674	10	1

\* NOTE: NOMINAL 10' PROVIDED FOR CONNECTIONS INSIDE BUILDING

PORTLAND CEMENT CONCRETE PAVEMENT 9" (SPECIAL)		
STATION TO STATION	SIDE	PCC PAVEMENT 9" (SPECIAL)
		SQ YD
<b>SOUTH MAIN STREET</b>		
COLLEGE INTERSECTION	LT/RT	213.0
MORGAN INTERSECTION	LT/RT	52.8
<b>COLLEGE AVENUE</b>		
SANDY INTERSECTION	LT/RT	161.4
MAUVAISTERRE INTERSECTION	LT/RT	75.3
<b>TOTAL</b>		502.5
<b>USE</b>		503

COMBINATION CONCRETE CURB AND GUTTER AND CONCRETE CURB				
STATION TO STATION	SIDE	COMBINATION CONCRETE CURB AND GUTTER, TYPE B6.12		CONCRETE CURB, TYPE B
		FOOT		FOOT
<b>SOUTH MAIN STREET</b>				
102+76.7	105+89.2	LT	312.5	
102+76.7	105+51.5	RT	274.8	
105+51.5	106+48.0	RT	107.6	
105+89.2	106+30.6	LT	42.3	
107+01.4	111+15.2	LT	427.6	
107+18.7	111+06.4	RT	400.2	
107+15.4	107+18.4	LT		9.8
107+39.1	107+57.1	RT		47.0
109+74.1	111+06.4	LT & RT	272.1	
<b>COLLEGE AVENUE</b>				
122+34.2	122+55.2	RT	32.8	
122+34.2	122+56.4	LT	33.2	
122+82.4	124+55.2	LT	191.1	
122+84.9	124+73.8	RT	209.4	
125+26.2	127+18.7	LT	216.4	
125+44.8	127+16.8	RT	189.0	
125+36.1	127+11.6	LT		413.8
127+44.7	127+58.7	LT	21.9	
127+48.6	127+65.8	RT	30.0	
<b>TOTAL</b>			2,760.9	470.6
<b>USE</b>			2,761	471

SIGNING SCHEDULE							
STATION	OFFSET	FACING	DESIGNATION	SIZE (L x W)	SIGN PANEL TYPE 1	TELESCOPING STEEL SIGNING SUPPORT (SPECIAL)	SIGN MESSAGE
				IN	SQ FT	FOOT	
<b>SOUTH MAIN STREET</b>							
111+02.3	25.9' RT	S	R1-1 (3030)	30 X 30	6.3	18	STOP
111+02.3	25.9' RT	S	R6-1 (R)	36 X 12	3.0	-	ONE WAY (ENCLOSED IN RIGHT ARROW)
107+41.8	33.3' RT	W	R5-1 (3030)	30 X 30	6.3	13	DO NOT ENTER
107+41.8	33.3' RT	E	R3-2 (3030)	30 X 30	6.3	-	NO LEFT TURN
107+58.9	36.4' RT	S	R7-8 W/ #250 FINE	12 X 18	1.5	12	RESERVED PARKING - #250 FINE
<b>COLLEGE AVENUE</b>							
122+41.9	22.6' RT	W	R1-1 (3030)	30 X 30	6.3	18	STOP
122+41.9	22.6' RT	W	R6-1 (R)	36 X 12	3.0	-	ONE WAY (ENCLOSED IN RIGHT ARROW)
122+41.9	22.6' RT	E	R6-1 (L)	36 X 12	3.0	-	ONE WAY (ENCLOSED IN LEFT ARROW)
122+52.6	33.0' LT	N	R1-1 (3030)	30 X 30	6.3	13	STOP
122+52.6	33.0' LT	S	R5-1 (3030)	30 X 30	6.3	-	DO NOT ENTER
122+84.7	33.0' LT	N	R1-1 (3030)	30 X 30	6.3	13	STOP
122+84.7	33.0' LT	S	R5-1 (3030)	30 X 30	6.3	-	DO NOT ENTER
122+97.8	21.3' LT	E	R1-1 (3030)	30 X 30	6.3	18	STOP
122+97.8	21.3' LT	W	R6-1 (R)	36 X 12	3.0	-	ONE WAY (ENCLOSED IN RIGHT ARROW)
122+97.8	21.3' LT	E	R6-1 (L)	36 X 12	3.0	-	ONE WAY (ENCLOSED IN LEFT ARROW)
127+09.7	20.8' RT	E	R6-2 (R)	24 X 30	5.0	13	ONE WAY WITH RIGHT ARROW
127+09.7	20.8' RT	W	R6-2 (L)	24 X 30	5.0	-	ONE WAY WITH LEFT ARROW
127+14.5	32.7' RT	S	R1-1 (3030)	30 X 30	6.3	13	STOP
127+14.5	32.7' RT	N	R5-1 (3030)	30 X 30	6.3	-	DO NOT ENTER
127+49.5	32.7' RT	S	R1-1 (3030)	30 X 30	6.3	13	STOP
127+49.5	32.7' RT	N	R5-1 (3030)	30 X 30	6.3	-	DO NOT ENTER
127+58.7	24.3' LT	E	R6-2 (R)	24 X 30	5.0	13	ONE WAY WITH RIGHT ARROW
127+58.7	24.3' LT	W	R6-2 (L)	24 X 30	5.0	-	ONE WAY WITH LEFT ARROW
<b>TOTALS</b>					118.4	157.0	
<b>USE</b>					119	157	

PAVING SCHEDULE							
STATION TO STATION	SUB-BASE GRANULAR MATERIAL, TYPE A, 4"	HOT-MIX ASPHALT BASE COURSE, 4 1/2"	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	LEVELING BINDER (MACHINE METHOD) N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)
				TON		GALLON	TON
<b>SOUTH MAIN STREET</b>							
102+02.58	102+76.69				65.2	49.9	1.0
102+76.69	105+51.47	98.0		7.0	107.8	82.4	1.7
105+51.47	105+89.17	15.5		8.8	14.4	11.3	0.2
107+60.13	108+75.92	38.0		1.2	47.0	34.8	0.7
108+75.92	109+50.00	27.7			29.0	22.2	0.5
109+50.00	109+80.10	133.8	114.1	16.0	11.2	8.6	0.2
109+80.10	110+87.60	479.8	286.7	40.1	28.1	21.5	0.4
110+87.60	111+16.2	150.4	59.6	8.3	5.8	4.5	0.1
<b>COLLEGE AVENUE</b>							
122+34.24	122+85.76	187.6			23.7	18.1	0.4
122+95.76	124+13.80	63.2		19.0	46.3	35.5	0.7
124+13.80	125+86.20	292.1	27.1	48.2	145.4	111.2	2.2
125+86.20	127+09.74	57.2		16.3	48.4	37.1	0.7
127+09.74	127+65.79	97.8		5.7	27.3	20.9	0.4
<b>PARKING LOTS</b>							
<b>NE QUADRANT OF SOUTH MAIN ST. AND COLLEGE AVE.</b>					100.7	77.1	1.5
<b>TOTAL</b>	1,641.1	460.4	91.5	106.2	700.3	535.1	10.9
<b>USE</b>	1,642	461	92	107	701	536	11